MP2608

28V, 1A Dual Input
Linear Battery Charger With Timer

The Future of Analog IC Technology

DESCRIPTION

The MP2608 is a dual-input, linear, high-performance low-cost single cell Li-Ion or Li-Polymer battery charger. It accepts two power inputs, one from a USB (Universal BUS) port and the other from an AC adapter. By integrating high voltage input protection into the charger IC, the MP2608 can tolerate an input surge up to 28V. Due to the protection inputs function, low-cost, large output tolerance adapters can be used safely.

The device features constant current (CC) and constant voltage (CV) charging modes with programmable charge currents (100mA to 1.0A), current blocking and trickle charge. The charge current for adapter input can be programmed by an external resistor, while the charge current for USB input is pre-set at 450mA.The device also provides charge status and fault indications to the system.

For guaranteed safe operation, the MP2608 folds back charge current when the device is heated up due to limited PCB space. Other safety features are including battery temperature monitoring, and programmable timer to complete the charging cycle.

MP2608 is available in a 10-pin 3mm x 3mm QFN package.

FEATURES

- Complete Solution for Charging Single-Cell Lion-Ion Battery
- Input Surge Up to 28V
- Adapter and USB Input
- Programmable Charge Current: 100mA to 1.0A
- Pre-set USB Charge Current: 450mA
- Proprietary Constant Voltage Auto Recharge
- Proprietary Over-Voltage Protection
- 0.75% V_{BATT} Accuracy over Temperature
- <1µA Battery Reverse Current
- 125µA Standby Current from V_{IN}
- Battery Temperature Monitoring
- Thermal Protection
- Fault and Charge Status Indicators
- Internal Soft-Start
- Tiny 3mm x 3mm QFN Package

APPLICATIONS

- Cell Phones
- Digital Cameras
- Smart Phones
- PDAs
- MP3 Players

TYPICAL APPLICATION

PACKAGE REFERENCE

TOP VIEW

IN	1		10	BATT
USB	2		9	ICHG
$\overline{FAULT}$	3		8	GND
$\overline{STATUS}$	4		7	TMR
SHDN	5		6	IBF

EXPOSED PAD — ON BACKSIDE

Part Number*	Package	Temperature
MP2608DQ	QFN10 (3mm x 3mm)	−40°C to +85°C

* For Tape & Reel, add suffix –Z (eg. MP2608DQ–Z)
For RoHS compliant packaging, add suffix –LF
(eg. MP2608DQ–LF–Z)

ABSOLUTE MAXIMUM RATINGS [1]

IN, USB to GND...........................–0.3V to +28V
All Other Pins to GND................–0.3V to +6.5V
Junction Temperature..............................140°C
Lead Temperature ....260°C
Storage Temperature ....–65°C to +150°C

Recommended Operating Conditions [2]
Nominal Supply Voltage V_{IN}...........3.5V to 5.5V
Operating Temperature ....–40°C to +85°C

Thermal Resistance [3] θ_{JA} θ_{JC}
3x3 QFN10 ....50 ...... 12... °C/W

Notes:
1) Exceeding these ratings may damage the device.
2) The device is not guaranteed to function outside of its operating conditions.
3) Measured on approximately 1" square of 1 oz copper.

ELECTRICAL CHARACTERISTICS

V_{IN} = 5V, V_{EN} = 0V, T_A = +25°C, unless otherwise noted.

Parameter	Symbol	Condition	Min	Typ	Max	Units
IN, USB Input Voltage	V_{IN}, V_{USB}		4.5		28	V
IN, USB Input Under-voltage Threshold	V_{IN-UV}	IN Input Rising	3.75	4	4.25	V
IN, USB Input Over-Voltage Threshold	V_{IN-OV}	IN Input Rising	5.8	6.0	6.2	V
Supply Current	I_{SUPPLY}	SHDN= Low and BATT floating			100	μA
		SHDN = High and BATT floating			80	
Charger						
Battery Voltage Regulation	V_{BATT}	T = +25°C, I_{BATT} = 0	4.179	4.200	4.221	V
		T = 0°C to +50°C, I_{BATT} = 0	4.168	4.200	4.232	
		T = –5°C to +75°C, I_{BATT} = 0	4.158	4.200	4.242	
Battery Over-Voltage Protection	I_{BATT_OVP}	V_{BATT} = 4.25V			0	μA
Constant Current Regulation	$I_{CHG,IN}$	V_{IN} = 5V, V_{BATT} = 3.8V R_{CHG} = 2.3kΩ	640	708	780	mA
	$I_{CHG,USB}$	V_{IN}=0V, V_{USB} = 5V, V_{BATT}=3.8V	410	450	490	mA
Constant Current Variation		V_{IN} = 5V, V_{BATT} = 3.8V, T_J = 0°C to +120°C, R_{CHG} = 1.6kΩ to 8.0kΩ	87	100	113	%I_{CHG} [4]

ELECTRICAL CHARACTERISTICS *(continued)*

V_{IN} = 5V, V_{EN} = 0V, T_A = +25°C, unless otherwise noted.

Parameter	Symbol	Condition	Min	Typ	Max	Units
Pass Device Drop-out Voltage	$V_{DROP,IN}$	$V_{IN,}$=4V, R_{CHG} = 1.5kΩ, 1A load on the BATT pin		130		mV
	$V_{DROP,USB}$	V_{USB} = 4V, 400mA load on the BATT pin		152		mV
Trickle Current		V_{IN} = 5V, V_{BATT} = 2.3V	5	10	15	%I_{CHG}[4]
IBF Accuracy			-20		+20	%IBF
Trickle Threshold Voltage			2.5	2.6	2.7	V
Trickle Voltage Hysteresis				100		mV
SHDN Trip High Threshold			2.0			V
SHDN Trip Low Threshold					0.4	V
SHDN Pull-down Resistor				500		kΩ
$\overline{FAULT}$, $\overline{STATUS}$ Sink Current		Pin Voltage = 0.4V	4			mA
Battery Reverse Current to BATT Pin		SHDN = High and Input = Floating or 0V			1	µA
Thermal Shutdown Threshold			105	120	135	°C
Thermal Shutdown Hysteresis				10		°C
Recharge Threshold						
Recharge Voltage Threshold	V_{RECHG}			4.0		V
Oscillator						
Oscillator Period	T_{OSC}	C_{TIME} = 15nF	4.8	6.0	7.2	ms
TIMEOUT Period	$T_{TIMEOUT}$			2^{15}		T_{OSC}

Notes:
4) I_{CHG} is the target preprogrammed charge current (Die temperature below 110°C).

PIN FUNCTIONS

Pin #	Name	Description
1	IN	Input Supply. IN receives the AC adapter supply voltage.
2	USB	Input Supply. USB receives the USB supply voltage.
3	$\overline{\text{FAULT}}$	Open-Drain Fault Status Indicator. This pin is low under any fault conditions.
4	$\overline{\text{STATUS}}$	Open-Drain Charge Indicator. This pin is low during charging.
5	SHDN	Charger IC Shut-down. Pull SHDN high to disable the IC or leave it floating to enable the IC.
6	IBF	Programmable Input for end of charger current.
7	TMR	Oscillator Period Timer. Connect a timing capacitor between this pin and GND to set the oscillator period. A 1uF capacitor on the TMR pin will make the oscillator period 400ms.
8	GND	Ground. Exposed pad and GND must connect to same ground plane.
9	ICHG	Constant Charge Current Program for the IN input. Connect this pin to an external resistor to program the charging current in CC Mode when the current from the IN pin charges the battery.
10	BATT	Charger Output.

TYPICAL PERFORMANCE CHARACTERISTICS

V_{IN}=5V, C_{IN}=2.2uF, C_{OUT}=1uF, R_{CHG}=2.21kΩ, T_A=25℃, unless otherwise noted.

Battery Charge Curve

Battery Charge Curve

Charge Current vs. Battery Voltage

Battery Voltage vs. Input Voltage

Charge Current vs. Battery Voltage

Charge Current vs. Input Voltage

Charge Current vs. R_{SET} Resistance

Reverse Current vs. Battery Voltage

TYPICAL PERFORMANCE CHARACTERISTICS *(continued)*

V$_{IN}$=5V, C$_{IN}$=2.2uF, C$_{OUT}$=1uF, R$_{CHG}$=2.21kΩ, T$_A$=25°C, unless otherwise noted.

Power On
(Adapter In)

Power On
(USB In)

Power Off
(Adapter In)

Power Off
(USB In)

Startup with $\overline{SD}$
(Adapter In)

Startup with $\overline{SD}$
(USB In)

Shutdown with $\overline{SD}$
(Adapter In)

Shutdown with $\overline{SD}$
(USB In)

6

TYPICAL PERFORMANCE CHARACTERISTICS *(continued)*

V_{IN}=5V, C_{IN}=2.2uF, C_{OUT}=1uF, R_{CHG}=2.21kΩ, T_A=25°C, unless otherwise noted.

Mode Exchange Waveform
(from USB In to Adapter In)

V_{USB}
2V/div

V_{BATT}
2V/div

V_{IN}
2V/div

I_{BATT}
200mA/div

200ms/div

Timer Out Waveform
(Ctimer=4.7nF)

V_{TIMR}
2V/div

V_{BATT}
2V/div

V_{FAULT}
2V/div

I_{BATT}
200mA/div

2ms/div

BLOCK DIAGRAM

Figure 1—Functional Block Diagram

8

OPERATION

Input Auto Selection and Voltage Range

The MP2608 is a dual-input charger, when both input sources are present, MP2608 selects only one power source to charge the battery. When the adapter input voltage is higher than the UVLO threshold, IN is selected as the power source. Otherwise the USB input is selected. If both the inputs is above UVLO but the adaptor input voltage is below the battery voltage, while the USB voltage is higher than the battery voltage, then the USB input is used to charge the battery.

In case there is no power source available or both the two input are below the UVLO, the MP2608 is in the sleep mode, in which the current into the BATT pin is reduced to TBD µA. The IC is also disabled to prevent the battery from draining.

The MP2608 has built-in input voltage surge protection as high as +28V. The charger IC will be automatically disabled when the input voltage is lower than 2.5V or higher than 6.0V.

Charge Cycle (Mode Change: Trickle -> CC-> CV)

Figure 2 below shows the typical charging profile for the MP2608. For a fully depleted battery with a terminal voltage lower than 2.6V, the MP2608 will start with the trickle charge (preconditioning) at 10% of the programmed full charge current. After the battery voltage reaches 2.6V, the charger begins charging at the constant current of the programmed value (I_{CHG}) and the charge timer starts counting down. This is referred to as Constant Current (CC) mode. Once the battery voltage reaches 4.2V, the charger will operate in the constant voltage (CV) mode until the battery is fully charged. The charge current drops during CV mode, and the battery full indication is set when the charge timer is time off. The charge timer is to protect the system from charging a dead battery for excessive long time.


Figure 2—MP2608 Typical Charging Profile

Charge Termination and Auto-Recharge

At any time when V_{BATT} is 50mV higher than the trimmed charge target, the MP2608 reduces its charge current to 0µA. This ensures the safety of the battery. Also, the CV control loop always monitors the battery voltage such that it will automatically recharge the battery when it is depleted below the target level.

Upon V_{BATT} drops to 4.0V, the charger will automatically restart the charge cycle until the end of the timeout. When the input adapter is unplugged, there is only 1µA leakage current from battery drawn by the MP2608.

Programming of Charge Current and Battery Full Current

The Charge Current (I_{CHG}) of Adaptor input can be programmed from 0.1A to 1A by a resistor (R_{CHG}) connecting from the ICHG pin to GND. The relationship of the charge current and the programming resistance is established by the following table and graph.

The recommended resistance for programming the charge current is TBD. The battery full charge current threshold (I_{BF})is programmed by connecting a resistor R_{BF} from the I_{BF} pin to GND:

$$I_{BF}=1A \times 1.7k\Omega/R_{BF}$$

When the USB is selected as the power source, the charge current is fixed at a pre-set value 450mA, which is a typical value of USB current.

Table 1—R_{CHG} and I_{CHG} Relationship

R_{CHG} (kΩ)	I_{CHG} (mA)
TBD	

TBD

Figure 3—Charge Current vs. 1/RPGM Resistance

Figure 4—MP2608 Typical Re-Charging Waveforms

Charge Status and Fault Indication

The open drain pin $\overline{STATUS}$ is used to indicate charging status. While battery is being charged, the $\overline{STATUS}$ pin is pulled low, when the battery full condition is reached or any other condition prevents the charger from charging, the $\overline{STATUS}$ pin will become a floating. $\overline{STATUS}$ is then latched till a new charge cycle is started.

Upon a time-out fault event happen, the $\overline{FAULT}$ pin is pulled low. When the V_{BATT} is lower than 2.6V for $1/8^{th}$ of timeout period or the charging can not reach EOC status before the timeout happens, this fault status is latched, the charging is suspended, and the $\overline{FAULT}$ pin is pulled low. To clear this fault, either the V_{IN} or V_{USB} should be recycled. One time-out period is equivalent to 2^{15} oscillator clock cycles. With a 1µF capacitor on the TMR pin, it takes 3.64 hours.

The Power On and recharge cycle are illustrated in Figure 4.

STATE DIAGRAM

NOTE: [ ] denotes the status of the PAD. Ex) [STATUS] means the STATUS pad is pulled-up. Low state is not specified in the bubble.

V_{POR}: Power-on-reset Threshold.
V_{TRK}: Trickle Charge Thres.
V_{RECH}: Recharge Thres.

Figure 5—MP2608 State Diagram

PACKAGE INFORMATION

QFN10 (3mm x 3mm)

PIN 1 ID
MARKING

PIN 1 ID
INDEX AREA

2.90
3.10

2.90
3.10

TOP VIEW

0.30
0.50

1.45
1.75

PIN 1 ID
SEE DETAIL A

0.18
0.30

10

0.50
BSC

6

1

2.25
2.55

5

BOTTOM VIEW

0.20 REF

0.80
1.00

0.00
0.05

SIDE VIEW

PIN 1 ID OPTION A
R0.20 TYP.

PIN 1 ID OPTION B
R0.20 TYP.

DETAIL A

2.90

0.70

1.70

0.25

0.50

2.50

RECOMMENDED LAND PATTERN

NOTE:

1) ALL DIMENSIONS ARE IN MILLIMETERS.
2) EXPOSED PADDLE SIZE DOES NOT INCLUDE MOLD FLASH.
3) LEAD COPLANARITY SHALL BE 0.10 MILLIMETER MAX.
4) DRAWING CONFORMS TO JEDEC MO-229, VARIATION VEED-5.
5) DRAWING IS NOT TO SCALE.