

SPEC

Spec No.	TQ3C-8EAF0-E1DDP32-01
Date	December 15, 2007

TYPE : TCG057VGLBB-G00

< 5.7 inch VGA transmissive color TFT
with LED backlight and touch panel >

CONTENTS

1. Application
2. Construction and outline
3. Mechanical specifications
4. Absolute maximum ratings
5. Electrical characteristics
6. Optical characteristics
7. Interface signals
8. Input timing characteristics
9. LED backlight characteristics
10. Design guidance for analog touch panel (T/P)
11. Lot number identification
12. Warranty
13. Precautions for use
14. Reliability test data
15. Outline drawing



KYOCERA CORPORATION
KAGOSHIMA HAYATO PLANT
LCD DIVISION

This specification is subject to change without notice.
Consult Kyocera before ordering.

Original Issue Date	Designed by: Engineering dept.			Confirmed by: QA dept.	
	Prepared	Checked	Approved	Checked	Approved
September 19, 2007	<i>J. Asano</i>	<i>Id. Ishimori</i>	<i>Y. Matsumoto</i>	<i>J. Sakaguchi</i>	<i>So. Ito</i>

Spec No. TQ3C-8EAF0-E1DDP32-01	Part No. TCG057VGLBB-G00	Page -
-----------------------------------	-----------------------------	-----------

Warning

1. This Kyocera LCD module has been specifically designed for use only in electronic devices and industrial machines in the area of audio control, office automation, industrial control home appliances, etc. The module should not be used in applications where the highest level of safety and reliability are required and module failure or malfunction of such module results in physical harm or loss of life, as well as enormous damage or loss. Such fields of applications include, without limitation, medical, aerospace, communications infrastructure, atomic energy control. Kyocera expressly disclaims any and all liability resulting in any way to the use of the module in such applications.
2. Customer agrees to indemnify, defend and hold Kyocera harmless from and against any and all actions, claims, damages, liabilities, awards, costs, and expenses, including legal expenses, resulting from or arising out of Customer's use, or sale for use, or Kyocera modules in applications.

Caution

1. Kyocera shall have the right, which Customer hereby acknowledges, to immediately scrap or destroy tooling for Kyocera modules for which no Purchase Orders have been received from the Customer in a two-year period.

Spec No. TQ3C-8EAF0-E1DDP32-01	Part No. TCG057VGLBB-G00	Page -
-----------------------------------	-----------------------------	-----------

Revision record

Date		Designed by : Engineering dept.			Confirmed by : QA dept.	
		Prepared	Checked	Approved	Checked	Approved
Dec. 15, 2007		<i>Y. Asano</i>	<i>Id. Ishimori</i>	<i>G. Matsumoto</i>	<i>J. Sakaguchi</i>	<i>K. Imai</i>
Rev.No.	Date	Page	Descriptions			
01	Dec. 15, 2007	1	2. Construction and outline ~ Add comment "Additional circuit"			
			3. Mechanical specifications ~ Change "Mass"			
		2	4. Absolute maximum ratings ~ Delete ()			
		3	5. Electrical characteristics ~ Delete () ~ Add "Current consumption value"			
		4	6. Optical characteristics ~ Delete () ~ Change all			
		9	9. LED backlight characteristics ~ Delete () ~ Change "Operating life time"			
		14	15. Outline Drawing ~ Change "121A5063100" → "121A5063100-1"			

1. Application

This document defines the specification of TCG057VGLBB-G00. (RoHS Compliant)

2. Construction and outline

LCD	: Transmissive color dot matrix type TFT
Backlight system	: LED
Polarizer	: Glare treatment
Additional circuit	: Timing controller, Power supply (3.3V input) (without constant current circuit for LED backlight)
Touch panel	: Analog type, Non-Glare treatment

3. Mechanical specifications

3-1. Mechanical specifications of LCD

Item	Specification	Unit
Outline dimensions	127.2 (W)× 100.4 (H) ×6.75 (D)	mm
Active area	115.2 (W) × 86.4 (H) (14.4cm / 5.7 inch (Diagonal))	mm
Dot format	640×(B,G,R) (W) × 480 (H)	dot
Dot pitch	0.06 (W) × 0.18 (H)	mm
Base color *1	Normally White	-
Mass	135	g

*1 Due to the characteristics of the LCD material, the color varies with environmental temperature.

3-2. Mechanical specifications of touch panel

Item	Specification	Unit
Input	Radius-0.8 stylus or Finger	-
Actuation Force	0.05 ~ 0.8	N
Transmittance	Typ. 79	%
Surface hardness	Pencil hardness 2H or more according	-
Anti newton's ring treatment	None	-

4. Absolute maximum ratings

4-1. Electrical absolute maximum ratings

Item	Symbol	Min.	Max.	Unit
Supply voltage for logic	V _{DD}	0	4.0	V
Input signal voltage *1	V _{IN}	-0.3	6.0	V
LED forward current *2	I _F	-	30	mA
Reversed voltage *2	V _R	-	5	V
Supply voltage for touch panel	V _{TP}	0	6.0	V
Input current of touch panel	I _{TP}	0	0.5	mA

*1 Input signal : CK, R0 ~ R5, G0 ~ G5, B0 ~ B5, H_{SYNC}, V_{SYNC}, ENAB, R/L, U/D

*2 For each “AN1-CA1”, “AN2-CA2” and “AN3-CA3” Temp. = 25°C

4-2. Environmental absolute maximum ratings

Item	Symbol	Min.	Max.	Unit
Operating temperature *1	T _{OP}	-20	70	°C
Storage temperature *2	T _{STO}	-30	80	°C
Operating humidity *3	H _{OP}	10	*4	%RH
Storage humidity *3	H _{STO}	10	*4	%RH
Vibration	-	*5	*5	-
Shock	-	*6	*6	-

*1 Operating temperature means a temperature which operation shall be guaranteed. Since display performance is evaluated at 25°C, another temperature range should be confirmed.

*2 Temp. = -30°C < 48h , Temp. = 80°C < 168h

Store LCD panels at normal temperature/humidity. Keep them free from vibration and shock.
An LCD panel that is kept at a low or a high temperature for a long time can be defective due to other conditions, even if the low or high temperature satisfies the standard.
(Please refer to “Precautions for Use” for details.)

*3 Non-condensing

*4 Temp. 40°C, 85%RH Max.

Temp. > 40°C, Absolute humidity shall be less than 85%RH at 40°C.

*5

Frequency	10 ~ 55 Hz	Acceleration value (0.3 ~ 9 m/s ²)
Vibration width	0.15mm	
Interval	10-55-10 Hz	1 minutes

2 hours in each direction X, Y, Z (6 hours total)

EIAJ ED-2531

*6 Acceleration: 490 m/s², Pulse width: 11 ms

3 times in each direction: ±X, ±Y, ±Z

EIAJ ED-2531

6. Optical characteristics


Measuring spot = ϕ 6.0mm, Temp. = 25°C

Item		Symbol	Condition	Min.	Typ.	Max.	Unit
Response time	Rise	τ_{r}	$\theta = \varphi = 0^{\circ}$	-	10	-	ms
	Down	τ_{d}	$\theta = \varphi = 0^{\circ}$	-	25	-	ms
Viewing angle range View deriction : 6 o'clock (Gray inversion)		θ_{UPPER}	CR 5	-	80	-	deg.
		θ_{LOWER}		-	80	-	
		φ_{LEFT}		-	80	-	deg.
		ϕ_{RIGHT}		-	80	-	
Contrast ratio		CR	$\theta = \varphi = 0^{\circ}$	300	500	-	-
Brightness		L	IF=15mA/Line	140	200	-	cd/m ²
Chromaticity coordinates	Red	x	$\theta = \varphi = 0^{\circ}$	0.56	0.61	0.66	-
		y		0.32	0.37	0.42	
	Green	x	$\theta = \varphi = 0^{\circ}$	0.29	0.34	0.39	
		y		0.52	0.57	0.62	
	Blue	x	$\theta = \varphi = 0^{\circ}$	0.09	0.14	0.19	
		y		0.06	0.11	0.16	
	White	x	$\theta = \varphi = 0^{\circ}$	0.28	0.33	0.38	
		y		0.30	0.35	0.40	


6-1. Definition of contrast ratio

$$\text{CR(Contrast ratio)} = \frac{\text{Brightness with all pixels "White"}}{\text{Brightness with all pixels "Black"}}$$


6-2. Definition of response time



6-3. Definition of viewing angle



6-4. Brightness measuring points



- 1) Rating is defined on the average in the viewing area.
- 2) Measured 30 minutes after the LED is powered on. (Ambient temp. = 25°C)

7. Interface signals

7-1. Pin assignment of LCD panel and LED

No.	Symbol	Description	I/O	Note
1	GND	GND	-	
2	CK	Clock signal for sampling each data signal	I	
3	H _{SYNC}	Horizontal synchronous signal (negative)	I	
4	V _{SYNC}	Vertical synchronous signal (negative)	I	
5	GND	GND	-	
6	R0	RED data signal (LSB)	I	
7	R1	RED data signal	I	
8	R2	RED data signal	I	
9	R3	RED data signal	I	
10	R4	RED data signal	I	
11	R5	RED data signal (MSB)	I	
12	GND	GND	-	
13	G0	GREEN data signal (LSB)	I	
14	G1	GREEN data signal	I	
15	G2	GREEN data signal	I	
16	G3	GREEN data signal	I	
17	G4	GREEN data signal	I	
18	G5	GREEN data signal (MSB)	I	
19	GND	GND	-	
20	B0	BLUE data signal (LSB)	I	
21	B1	BLUE data signal	I	
22	B2	BLUE data signal	I	
23	B3	BLUE data signal	I	
24	B4	BLUE data signal	I	
25	B5	BLUE data signal (MSB)	I	
26	GND	GND	-	
27	ENAB	Signal to settle the horizontal display position (positive)	I	*1
28	V _{DD}	3.3V power supply	-	
29	V _{DD}	3.3V power supply	-	
30	R/L	Horizontal display mode select signal L : Normal , H : Left / Right reverse mode	I	*2
31	U/D	Vertical display mode select signal H : Normal , L : Up / Down reverse mode	I	*2
32	NC	No connect	-	
33	CA1	Cathode 1	-	
34	CA2	Cathode 2	-	
35	CA3	Cathode 3	-	
36	NC	No connect	-	
37	AN1	Anode 1	-	
38	AN2	Anode 2	-	
39	AN3	Anode 3	-	
40	NC	No connect	-	

LCD connector : IMSA-9681S-40A-GF (IRISO)

Recommended matching FFC or FPC : 0.5mm pitch

*1 The horizontal display start timing is settled in accordance with a rising timing of ENAB signal.
In case ENAB is fixed "Low", the horizontal start timing is determined.
Don't keep ENAB "High" during operation.

*2



R/L = L
U/D = H



R/L = H
U/D = H



R/L = L
U/D = L



R/L = H
U/D = L

7-2. Pin assignment of touch panel

No.	Symbol	Description
1	yL	y-Lower terminal
2	xL	x-Left terminal
3	yU	y-Upper terminal
4	xR	x-Right terminal

Touch panel side connector : 1.25mm pitch
Recommended matching connector : Series FE, FFS (JST)
: KCA-K4R (DMC)

8. Input timing characteristics

8-1. Timing characteristics


Item		Symbol	Min	Typ	Max	Unit	Note
Clock	Frequency	1/Tc	-	25.18	28.88	MHz	
	Duty ratio	Tch/Tc	40	50	60	%	
Data	Set up time	Tds	10	-	-	ns	
	Hold time	Tdh	10	-	-	ns	
Horizontal sync. signal	Cycle	TH	30.0	31.8	-	μs	
			770	800	900	clock	
	Pulse width	THp	5	30	-	clock	
	Set up time	THs	10	-	-	ns	
	Hold time	THh	10	-	-	ns	
Vertical sync. signal	Cycle	TV	515	525	560	line	
	Pulse width	TVp	1	3	5	line	
	Set up time	TVs	10	-	-	ns	
	Hold time	TVh	10	-	-	ns	
Enable signal (ENAB)	Pulse width	TEp	640			clock	
	Set up time	TEs	10	-	-	ns	
	Hold time	TEh	10	-	-	ns	
H _{SYNC} - Enable signal phase difference		THE	112	144	175	clock	
H _{SYNC} - V _{SYNC} signal phase difference		THV	10	-	-	ns	
Vertical sync. signal start position		TVE	2	35	76	line	
Horizontal display period		THd	640			clock	
Vertical display period		TVd	480			line	

*When ENAB is fixed at "Low", the horizontal display starts from the data of C144 (clock) as shown in 8-3.


*When ENAB is fixed at "Low", the vertical sync. signal start position is 35 (line) as shown in 8-3.

*In case of lower frequency, the deterioration of the display quality, flicker etc., may occur.

8-2. Input Data Signals and Display position on the screen



8-3. Input timing characteristics



*1 When ENAB is fixed at "Low", the horizontal display starts from the data of C144 (clock).

*2 When ENAB is fixed at "Low", the vertical sync. signal start position is 35 (line).

9. LED backlight characteristics

LED ratings

Item	Symbol	Min.	Typ.	Max.	Unit	Note
Forward current *1	IF	-	15	-	mA	Ta=-20 ~ 70°C
Forward voltage *1	VF	-	22.1	25.0	V	IF=15mA, Ta=-20
		-	21.7	24.5	V	IF=15mA, Ta=25
		-	21.3	24.1	V	IF=15mA, Ta=70
Operating life time *2, *3	T	-	40,000	-	h	IF=15mA, Ta=25

*1 For each "AN1-CA1", "AN2-CA2" and "AN3-CA3"

*2 When brightness decrease 50% of initial brightness.

*3 Life time is estimated data. (Condition : IF=15mA, Ta=25 in chamber).

* An input current below 5.0mA may reduce the brightness uniformity of the LED backlight. This is because the amount of light from each LED chip is different. Therefore, please evaluate carefully before finalizing the input current.

10. Design guidance for analog touch panel (T/P)

10-1 Electrical (In customer's design, please remember the following considerations.)

- 1 Do not use the current regulated circuit.
- 2 Keep the current limit with top and bottom layer. (Please refer to “Electrical absolute maximum ratings” for details.)
- 3 Analog T/P can not sense two points touching separately.
- 4 A contact resistance is appeared at the touch point between top and bottom layer.
After this resistance has stable read of the T/P position data.
- 5 Because noise of inverter or peripheral circuits may interfere signal of touch panel itself it is necessary to design carefully in advance to avoid these noise problem.

10-2 Software

- 1 Do the "User Calibration".
- 2 "User Caribration" may be needed with long term using.
Include "User Caribration" menu in your software.
- 3 When drawing a line with a stylus, there may be a slight discontinuity when the stylus passes over a spacer-dot. If necessary, please provide a compensation feature within your software.

10-3 Mounting on display and housing bezel

- 1 Do not use an adhesive tape to bond it on the front of T/P and hang it to the housing bezel.
- 2 Never expand the T/P top layer (PET-film) like a balloon by internal air pressure.
The life of the T/P will be extremely short.
- 3 If a dew will be on the heat-sealed area or exposed traces at the end of a flexible tail, the migration of silver can occur. This will cause sometimes a short circuit.

11. Lot number identification

The lot number shall be indicated on the back of the backlight case of each LCD.

TCG057VGLBB-G00 - □□ - □□ - □ MADE IN □□□□□

↓ ↓ ↓ ↓ ↓
1 2 3 4 5

No1. - No5. above indicate
 1. Year code
 2. Month code
 3. Date
 4. Version Number
 5. Country of origin (Japan or China)

Year	2007	2008	2009	2010	2011	2012
Code	7	8	9	0	1	2

Month	Jan.	Feb.	Mar.	Apr.	May	Jun.
Code	1	2	3	4	5	6

Month	Jul.	Aug.	Sep.	Oct.	Nov.	Dec.
Code	7	8	9	X	Y	Z

12. Warranty

12-1. Incoming inspection

Please inspect the LCD within one month after your receipt.

12-2. Production warranty

Kyocera warrants its LCD's for a period of 12 months from the ship date. Kyocera shall, by mutual agreement, replace or re-work defective LCD's that are shown to be Kyocera's responsibility.

13. Precautions for use

13-1. Installation of the LCD

- 1) The LCD shall be installed so that there is no pressure on the LSI chips.
- 2) The LCD shall be installed flat, without twisting or bending.
- 3) Must maintain a gap between inside of bezel and touch panel to avoid malfunction or electrode damage of touch panel.

13-2. Static electricity

- 1) Since CMOS ICs are mounted directly onto the LCD glass, protection from static electricity is required.
- 2) Workers should use body grounding. Operator should wear ground straps.

13-3. LCD operation

- 1) The LCD shall be operated within the limits specified. Operation at values outside of these limits may shorten life, and/or harm display images.

13-4. Storage

- 1) The LCD shall be stored within the temperature and humidity limits specified.
Store in a dark area, and protect the LCD from direct sunlight or fluorescent light.
- 2) Always store the LCD so that it is free from external pressure onto it.

13-5. Usage

- 1) **DO NOT** store in a high humidity environment for extended periods. Polarizer degradation bubbles, and/or peeling off of the polarizer may result.
- 2) Do not push or rub the touch panel's surface with hard to sharp objects such as knives, or the touch panel may be scratched.
- 3) When the touch panel is dirty, gently wipe the surface with a soft cloth, sometimes moistened by mild detergent or alcohol. If a hazardous chemical is dropped on the touch panel by mistake, wipe it off right away to prevent human contact.
- 4) Touch panel edges are sharp. Handle the touch panel with enough care to prevent cuts
- 5) Always keep the LCD free from condensation during testing. Condensation may permanently spot or stain the polarizer.
- 6) Do not disassemble LCD module because it will result in damage.
- 7) This Kyocera LCD module has been specifically designed for use in general electronic devices, but not for use in a special environment such as usage in an active gas. Hence, when the LCD is supposed to be used in a special environment, evaluate the LCD thoroughly beforehand and do not expose the LCD to chemicals such as an active gas.
- 8) Please do not use solid-base image pattern for long hours because a temporary afterimage may appear. We recommend using screen saver etc. in cases where a solid-base image pattern must be used.
- 9) Liquid crystal may leak when the module is broken. Be careful not to let the fluid go into your eyes and mouth. In the case the fluid touches your body; rinse it off right away with water and soap.

14. Reliability test data

Test item	Test condition	Test time	Judgement
High temp. atmosphere	80°C	240h	Display function : No defect Display quality : No defect Current consumption : No defect
Low temp. atmosphere	-30°C	240h	Display function : No defect Display quality : No defect Current consumption : No defect
High temp. humidity atmosphere	40°C 90% RH	240h	Display function : No defect Display quality : No defect Current consumption : No defect
Temp. cycle	-30°C 0.5h R.T. 0.5h 80°C 0.5h	10cycles	Display function : No defect Display quality : No defect Current consumption : No defect
High temp. operation	70°C	500h	Display function : No defect Display quality : No defect Current consumption : No defect
Point Activation life	Polyacetal stylus (R0.8) Hitting force 3N Hitting speed 2 time/s	one million times	Terminal resistance : No defect Insulation resistance : No defect Linearity : No defect Actuation Force : No defect

* Each test item uses a test LCD only once. The tested LCD is not used in any other tests.






* The LCD is tested in circumstances in which there is no condensation.

* The reliability test is not an out-going inspection.

* The result of the reliability test is for your reference purpose only.

The reliability test is conducted only to examine the LCD's capability.

No	Description	Drawn	Checked	Checked	Approved
△	・Add DETAIL E.	'07.12.01 倉元	'07.12.02 鶴崎		'07.12.03 南



- Note. (注記)
- Connector CN1: IMSA-9681S-40A-GF (IRISO) (コネクタ)
 - The Information of LCD is displayed starting at the upper left hand corner, moving right then down to the lower right hand corner. (LCDにおいて、画像データの表示は左上コーナーから始まり、右へ進み下へ送られ右下コーナーへ向かう。)
 - Tolerance without indication: ±0.5 (指示無き公差)

Material	Treatment	Approved	Checked	Checked	Drawn	Scale	Title	Year-Month-Day	Size
材質	処理	'07.09.07		'07.09.07	倉元	1:1(5:1,NTS)	TCG057VGLBB	'07.09.07	2
Quantity	Description:	南	茶園				Outline Dimensions		1
製作数	備考								2

Drawing No.	Year-Month-Day	Size
121A5063100-1	'07.09.07	2

Spec No.	TQ3C-8EAF0-E2DDP32-00
Date	September 19, 2007

KYOCERA INSPECTION STANDARD

TYPE : TCG057VGLBB-G00

KYOCERA CORPORATION
KAGOSHIMA HAYATO PLANT
LCD DIVISION

Original Issue Date	Designed by : Engineering dept.			Confirmed by : QA dept.	
	Prepared	Checked	Approved	Checked	Approved
September 19, 2007	<i>Y. Yamaguchi</i>	<i>W. John</i>	<i>Y. Matsumoto</i>	<i>J. Sakaguchi</i>	<i>Lo. [Signature]</i>

Spec No.

TQ3C-8EAF0-E2DDP32-00

Part No.

TCG057VGLBB-G00

Page

-

Revision record

Date		Designed by : Engineering dept.			Confirmed by : QA dept.	
		Prepared	Checked	Approved	Checked	Approved
Rev.No.	Date	Page	Descriptions			




Visuals specification

1) Note

	Note																													
General	1. Customer identified anomalies not defined within this inspection standard shall be reviewed by Kyocera, and an additional standard shall be determined by mutual consent. 2. This inspection standard about the image quality shall be applied to any defect within the active area and shall not be applicable to outside of the area. 3. Inspection conditions Luminance : 500 Lux min. Inspection distance : 300 mm. Temperature : 25 ± 5 Direction : Directly above																													
Definition of inspection item	Dot defect	Bright dot defect	The dot is constantly “on” when power applied to the LCD, even when all “Black” data sent to the screen. Inspection tool: 5% Transparency neutral density filter. Count dot: If the dot is visible through the filter Don't count dot: If the dot is not visible through the filter filter <table><tr><td>R</td><td>G</td><td>B</td><td>R</td><td>G</td><td>B</td><td>R</td><td>G</td><td>B</td></tr><tr><td>R</td><td>G</td><td>B</td><td>R</td><td>G</td><td>B</td><td>R</td><td>G</td><td>B</td></tr><tr><td>R</td><td>G</td><td>B</td><td>R</td><td>G</td><td>B</td><td>R</td><td>G</td><td>B</td></tr></table> dot defect	R	G	B	R	G	B	R	G	B	R	G	B	R	G	B	R	G	B	R	G	B	R	G	B	R	G	B
		R	G	B	R	G	B	R	G	B																				
		R	G	B	R	G	B	R	G	B																				
	R	G	B	R	G	B	R	G	B																					
	Black dot defect	The dot is constantly “off” when power applied to the LCD, even when all “White” data sent to the screen.																												
	Adjacent dot	Adjacent dot defect is defined as two or more bright dot defects or black dot defects. dot defect																												
External inspection	Bubble, Scratch, Foreign particle (Polarizer, Cell, Backlight)	Visible operating (all pixels “Black” or “White”) and non operating.																												
	Appearance inspection	Does not satisfy the value at the spec.																												
Others	LED wire	Damaged to the LED wire, connector, pin, functional failure or appearance failure.																												
Definition of size	Definition of circle size $d = (a + b)/2$ Definition of linear size																													

2) Standard

Classification		Inspection item		Judgement standard																																	
Defect (in LCD glass)	Dot defect	Bright dot defect		Acceptable number		: 4																															
				Bright dot spacing		: 5 mm or more																															
		Black dot defect		Acceptable number		: 5																															
				Bright dot spacing		: 5 mm or more																															
		2 dot join	Bright dot defect	Acceptable number		: 2																															
			Black dot defect	Acceptable number		: 3																															
	3 or more dots join		Acceptable number		: 0																																
	Total dot defects		Acceptable number		: 5 Max																																
	Others	White dot, Dark dot (Circle)		<table><tr><th colspan="2">Size (mm)</th><th colspan="2">Acceptable number</th></tr><tr><td>d</td><td>0.2</td><td colspan="2">(Neglected)</td></tr><tr><td>0.2 < d</td><td>0.4</td><td colspan="2">5</td></tr><tr><td>0.4 < d</td><td>0.5</td><td colspan="2">3</td></tr><tr><td>0.5 < d</td><td></td><td colspan="2">0</td></tr></table>				Size (mm)		Acceptable number		d	0.2	(Neglected)		0.2 < d	0.4	5		0.4 < d	0.5	3		0.5 < d		0											
Size (mm)		Acceptable number																																			
d	0.2	(Neglected)																																			
0.2 < d	0.4	5																																			
0.4 < d	0.5	3																																			
0.5 < d		0																																			
External inspection (Defect on Polarizer or between Polarizer and LCD glass)		Polarizer (Scratch)		<table><tr><th colspan="2">Width (mm)</th><th colspan="2">Length (mm)</th><th colspan="2">Acceptable number</th></tr><tr><td>W</td><td>0.1</td><td colspan="2">-</td><td colspan="2">(Neglected)</td></tr><tr><td rowspan="2">0.1 < W</td><td rowspan="2">0.3</td><td colspan="2">L 5.0</td><td colspan="2">(Neglected)</td></tr><tr><td colspan="2">5.0 < L</td><td colspan="2">0</td></tr><tr><td colspan="2">0.3 < W</td><td colspan="2">-</td><td colspan="2">0</td></tr></table>				Width (mm)		Length (mm)		Acceptable number		W	0.1	-		(Neglected)		0.1 < W	0.3	L 5.0		(Neglected)		5.0 < L		0		0.3 < W		-		0			
				Width (mm)		Length (mm)		Acceptable number																													
				W	0.1	-		(Neglected)																													
				0.1 < W	0.3	L 5.0		(Neglected)																													
						5.0 < L		0																													
		0.3 < W		-		0																															
		Polarizer (Bubble)		<table><tr><th colspan="2">Size (mm)</th><th colspan="2">Acceptable number</th></tr><tr><td>d</td><td>0.2</td><td colspan="2">(Neglected)</td></tr><tr><td>0.2 < d</td><td>0.3</td><td colspan="2">5</td></tr><tr><td>0.3 < d</td><td>0.5</td><td colspan="2">3</td></tr><tr><td>0.5 < d</td><td></td><td colspan="2">0</td></tr></table>				Size (mm)		Acceptable number		d	0.2	(Neglected)		0.2 < d	0.3	5		0.3 < d	0.5	3		0.5 < d		0											
				Size (mm)		Acceptable number																															
				d	0.2	(Neglected)																															
				0.2 < d	0.3	5																															
				0.3 < d	0.5	3																															
		0.5 < d		0																																	
		Foreign particle (Circle shape)		<table><tr><th colspan="2">Size (mm)</th><th colspan="2">Acceptable number</th></tr><tr><td>d</td><td>0.2</td><td colspan="2">(Neglected)</td></tr><tr><td>0.2 < d</td><td>0.4</td><td colspan="2">5</td></tr><tr><td>0.4 < d</td><td>0.5</td><td colspan="2">3</td></tr><tr><td>0.5 < d</td><td></td><td colspan="2">0</td></tr></table>				Size (mm)		Acceptable number		d	0.2	(Neglected)		0.2 < d	0.4	5		0.4 < d	0.5	3		0.5 < d		0											
				Size (mm)		Acceptable number																															
				d	0.2	(Neglected)																															
				0.2 < d	0.4	5																															
				0.4 < d	0.5	3																															
		0.5 < d		0																																	
Foreign particle (Linear shape) Scratch		<table><tr><th colspan="2">Width (mm)</th><th colspan="2">Length (mm)</th><th colspan="2">Acceptable number</th></tr><tr><td>W</td><td>0.03</td><td colspan="2">-</td><td colspan="2">(Neglected)</td></tr><tr><td rowspan="3">0.03 < W</td><td rowspan="3">0.1</td><td colspan="2">L 2.0</td><td colspan="2">(Neglected)</td></tr><tr><td colspan="2">2.0 < L 4.0</td><td colspan="2">3</td></tr><tr><td colspan="2">4.0 < L</td><td colspan="2">0</td></tr><tr><td colspan="2">0.1 < W</td><td colspan="2">-</td><td colspan="2">(According to circular shape)</td></tr></table>				Width (mm)		Length (mm)		Acceptable number		W	0.03	-		(Neglected)		0.03 < W	0.1	L 2.0		(Neglected)		2.0 < L 4.0		3		4.0 < L		0		0.1 < W		-		(According to circular shape)	
		Width (mm)		Length (mm)		Acceptable number																															
		W	0.03	-		(Neglected)																															
		0.03 < W	0.1	L 2.0		(Neglected)																															
				2.0 < L 4.0		3																															
				4.0 < L		0																															
		0.1 < W		-		(According to circular shape)																															

Inspection item	Judgement standard					
Scratch, Foreign particle (Touch screen portion)	(W = Width, L = Length, D = Diameter = (major axis + minor axis)/ 2)					
	Item	Width(mm)		Length(mm)	Acceptable number	
	Scratch	0.08 < d 0.1		L 4	1pces within ϕ 30mm	
		0.05 < d 0.08		L 6	2pces within ϕ 20mm	
		0.03 < d 0.05		L 10	2pces within ϕ 20mm	
		d 0.03		L 20	Neglected	
	Foreign (line like)	0.05 < W 0.1		L 5	2pces within ϕ 30mm	
		W 0.05		Neglected	Neglected	
	Foreign (circle like)	0.2 < D 0.3		2pces within ϕ 30mm		
		D 0.2		Neglected		
Above are applied to the visible area.						
Unless there are foreign particle and damage affected seriously to the electrical performance out of the active area, we approve of this product.						
Glass crack (Touch screen portion)	Item	Size (mm)			Acceptable number	
	Conner crack				X 3	2 pcs /panel
					Y 3	
					Z < t	
	Crack in other area than in corner				X 5	2 pcs /side
					Y 1.5	
					Z < t	
	Progressive crack				0 pcs (NG even 1pcs)	
	Above are applied to the visible area.					
	Unless there are foreign particle and damage affected seriously to the electrical performance out of the active area, we approve of this product.					
Newton's ring	Neglected. 