



For most current data sheet and other product information, visit www.burr-brown.com

# Single-Supply, Rail-to-Rail Output, CMOS **INSTRUMENTATION AMPLIFIER**

## **FEATURES**

- RAIL-TO-RAIL OUTPUT SWING: Within 10mV
- LOW OFFSET VOLTAGE: ±200µV
- LOW OFFSET DRIFT: ±5µV/°C
- INTERNAL FIXED GAIN = 10V/V OR 50V/V
- SPECIFIED TEMPERATURE RANGE: -55°C to +125°C
- LOW INPUT BIAS CURRENT: 0.2pA
- WIDE BANDWIDTH: 550kHz in G = 10
- HIGH SLEW RATE: 6.5V/µs
- LOW COST
- SO-8 AND TINY MSOP-8 PACKAGES

# APPLICATIONS

- INDUSTRIAL SENSOR AMPLIFIERS Bridge, RTD, Thermocouple, Flow, Position
- MEDICAL EQUIPMENT ECG, EEG, EMG Amplifiers
- DRIVING A/D CONVERTERS
- PCMCIA CARDS
- AUDIO PROCESSING
- COMMUNICATIONS
- TEST EQUIPMENT
- LOW COST AUTOMOTIVE INSTRUMENTATION

# DESCRIPTION


The INA155 is a low-cost CMOS instrumentation amplifier with rail-to-rail output swing optimized for low voltage, single-supply operation.

Wide bandwidth (550kHz in G = 10) and high slew rate (6.5V/µs) make the INA155 suitable for driving sampling A/D converters as well as general purpose and audio applications. Fast settling time allows use with higher speed sensors and transducers and rapid scanning data acquisition systems.

Gain can be set to 10V/V or 50V/V by pin strapping. Gains between these two values can be obtained with the addition of a single resistor. The INA155 is fully specified over the supply range of +2.7 to +5.5V.

The INA155 is available in MSOP-8 and SO-8 surface-mount packages. Both are specified for operation over the temperature range -55°C to 125°C.

Printed in U.S.A. February, 2000



International Airport Industrial Park • Mailing Address: PO Box 11400, Tucson, AZ 85734 • Street Address: 6730 S. Tucson Blvd., Tucson, AZ 85706 • Tel: (520) 746-1111 Twx: 910-952-1111 • Internet: http://www.burr-brown.com/ • Cable: BBRCORP • Telex: 066-6491 • FAX: (520) 889-1510 • Immediate Product Info: (800) 548-6132

PDS-1529B

# SPECIFICATIONS: $V_S = +2.7V$ to +5.5V

Boldface limits apply over the specified temperature range,  $T_A = -40^{\circ}C$  to  $+85^{\circ}C$ 

At  $T_A$  = +25°C,  $R_L$  = 10k $\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.

				INA155E, U	ı	18	NA155EA, U	IΔ	
DADAMETED		CONDITION			1				
PARAMETER		CONDITION	MIN	TYP	MAX	MIN	TYP	MAX	UNITS
INPUT									
Offset Voltage, RTI	$V_{OS}$	$V_S = +5.0V, V_{CM} = V_S/2$		±0.2	±1		*	*	mV
Over Temperature					±1.5			*	mV
	$dV_{OS}/d_{T}$			±5			*		μV/°C
vs Power Supply	PSRR	$V_S = +2.7V \text{ to } +6V, V_{CM} = 0.2 \bullet V_S$		±50	±200		*	*	μV/V
Over Temperature					±250			*	μV/V
vs Time				±0.4			*		μV/mo
INPUT VOLTAGE RANGE									
Safe Input Voltage			(V-) - 0.5		(V+) + 0.5	*		*	V
Common-Mode Range <sup>(1)</sup>	$V_{CM}$	$V_{S} = 5.5V$	0.3		5.2(2)	*		*	V
		V <sub>S</sub> = 2.7V	0.2		2.5(2)	*		*	V
Common-Mode Rejection Ratio	CMRR	$V_S = 5.5V$ , $0.6V < V_{CM} < 3.7V$ , $G = 10$	92	100		80	*		dB
Over Temperature			85			79			dB
		$V_S = 5.5V, 0.6V < V_{CM} < 3.7V, G = 50$	86	90		77	*		dB
Over Temperature			85			76			dB
INPUT IMPEDANCE									
Differential				10 <sup>13</sup>    3			*		Ω    pF
Common-Mode				10 <sup>13</sup>    3			*		Ω    pF
				10    0			-4-		22    Pi
INPUT BIAS CURRENT				14	140			34	
Input Bias Current	Ι <sub>Β</sub>			±1 ±1	±10		*	*	pA
Offset Current	I <sub>os</sub>			±1	±10		*	*	pA
NOISE, RTI		$R_S = 0\Omega$ , $G = 10 \text{ or } 50$							
Voltage Noise: f = 0.1Hz to 10Hz				4.5			*		μV/Vp-p
Voltage Noise Density: f = 10Hz				260			*		nV/√Hz
f = 100Hz				99			*		nV/√ <del>Hz</del>
f = 1kHz				40			*		nV/√Hz
Current Noise: f = 1kHz				2			*		fA/√Hz
GAIN			10		50	*		*	V/V
Gain Equation			G = 1	0 + 400kΩ/(	Ų.		*		V/V
Gain Error <sup>(3)</sup>		$V_S = 5.5V$ , $V_O = 0.01V$ to 5.49V, $G = 10$		±0.02	±0.1		*	*	%
vs Temperature				±2	±10		*	*	ppm/°C
		$V_S = 5.5V$ , $V_O = 0.05V$ to 5.45V, $G = 50$		±0.05	±0.25		*	*	%
vs Temperature				±15	±30		*	*	ppm/°C
Nonlinearity		$V_S = 5.5V, G = 10 \text{ or } 50$		±0.005	±0.015		*	*	% of FSR
Over Temperature					±0.015			*	% of FSR
OUTPUT									
Voltage Output Swing from Rail		$R_L = 10k\Omega, G_{ERR} < 0.1\%$		5	10		*	*	mV
Over Temperature					10			*	mV
Short-Circuit Current		Short Circuit to Ground		±50			*		mA
Capacitance Load (stable operation)			Se	e Typical Cu	irve		*		
FREQUENCY RESPONSE									
Bandwidth, -3dB	BW	G = 10		550			*		kHz
		G = 50		110			*		kHz
Slew Rate	SR			6.5			*		V/μs
Settling Time: 0.1%	$t_S$	$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 10$		5			*		μs
		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 50$		11			*		μs
0.01%		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 10$		8			*		μs
		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 50$		15			*		μs
Overload Recovery		50% Input Overload	_	0.2			*		μs
	THD+N		Se	e Typical Cu	ırve		*		
POWER SUPPLY									1
Specified Voltage Range			+2.7		+5.5	*		*	V
Operating Voltage Range				+2.5 to +6			*		V
Quiescent Current		$V_{IN} = 0, I_{O} = 0$		1.7	2.1		*	*	mA
Over Temperature		$V_{IN}=0,\ I_O=0$			2.6			*	mA
TEMPERATURE RANGE									
Specified Range			-40		+85	*		*	°C
Operating Range			-65		+150	*		*	°C
		I	-65	1	+150	*	1	*	°C
Storage Range				l				1 -	
Thermal Resistance	$ heta_{\sf JA}$								
	$ heta_{\sf JA}$			150 150			*		°C/W

<sup>\*</sup> Same as INA155E, U.

NOTES: (1) For further information, refer to typical performance curves on common-mode input range. (2) Operation above (V+) - 1.8V (max) results in reduced common-mode rejection. See discussion and Figure 6 in the text of this data sheet. (3) Does not include error and TCR of additional optional gain-setting resistor in series with  $R_g$ , if used.



# SPECIFICATIONS: $V_S = +2.7V$ to +5.5V

**Boldface** limits apply over the specified temperature range,  $T_A = -55^{\circ}C$  to  $+125^{\circ}C$ 

At  $T_A$  = +25°C,  $R_L$  = 10k $\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.


				NA155E, L	J	II.			
PARAMETER		CONDITION	MIN	TYP	MAX	MIN	TYP	MAX	UNITS
INPUT									
Offset Voltage, RTI	Vos	$V_S = +5.0V, V_{CM} = V_S/2$		±0.2	±1		*	*	mV
Over Temperature	00	, om 6			±2			*	mV
Drift	$dV_{OS}/d_{T}$			±5			*		μV/°C
vs Power Supply	PSRR	$V_S = +2.7V \text{ to } +6V, V_{CM} = 0.2 \cdot V_S$		±50	±200		*	*	μV/V
Over Temperature		S S S S S S S S S S S S S S S S S S S			±250			*	μV/V
vs Time				±0.4			*		μV/mo
INPUT VOLTAGE RANGE									1
Safe Input Voltage			(V-) - 0.5		(V+) + 0.5	*		*	V
Common-Mode Range <sup>(1)</sup>	$V_{CM}$	V <sub>S</sub> = 5.5V	0.3		5.2 <sup>(2)</sup>	*		*	V
Common-wode Range	v CM	$V_{S} = 3.3V$ $V_{S} = 2.7V$	0.3		2.5 <sup>(2)</sup>	*		*	l v
Common-Mode Rejection Ratio	CMDD	$V_S = 2.7 \text{ V}$ $V_S = 5.5 \text{V}, 0.6 \text{V} < V_{CM} < 3.7 \text{V}, G = 10$	92	100	2.5	80	*	~	dB
Over Temperature	CIVIKK	$V_{\rm S} = 5.5  \text{V}, \ 0.6  \text{V} < V_{\rm CM} < 5.7  \text{V}, \ G = 10$	82 82	100		78	~		dB
Over remperature		$V_S = 5.5V, 0.6V < V_{CM} < 3.7V, G = 50$	86	90		7 <b>6</b> 77	*		dB dB
O T		$v_S = 5.5 \text{ v}, 0.6 \text{ v} < v_{CM} < 5.7 \text{ v}, G = 50$		90			*		
Over Temperature			84			76			dB
INPUT IMPEDANCE				40					l <u>-</u>
Differential				10 <sup>13</sup>    3			*		Ω    pF
Common-Mode				1013    3			*		Ω    pF
INPUT BIAS CURRENT									1
Input Bias Current	I <sub>B</sub>			±1	±10		*	*	pA
Offset Current	Ios			±1	±10		*	*	pА
NOISE, RTI		$R_S = 0\Omega$ , $G = 10 \text{ or } 50$							
Voltage Noise: f = 0.1Hz to 10Hz				4.5			*		μV/Vp-p
Voltage Noise Density: f = 10Hz				260			*		nV/√ <del>Hz</del>
f = 100Hz				99			*		nV/√ <del>Hz</del>
f = 1kHz				40			*		nV/√Hz
Current Noise: f = 1kHz				2			*		fA/√Hz
GAIN			10		50	*		*	V/V
Gain Equation			G = 10	$0 + 400 k\Omega/(1$	$10k\Omega + R_G$		*		V/V
Gain Error <sup>(3)</sup>		$V_S = 5.5V$ , $V_O = 0.01V$ to 5.49V, $G = 10$		±0.02	±0.1		*	*	%
vs Temperature				<b>±2</b>	±10		*	*	ppm/°C
		$V_S = 5.5V$ , $V_O = 0.05V$ to 5.45V, $G = 50$		±0.05	±0.25		*	*	%
vs Temperature				±15	±30		*	*	ppm/°C
Nonlinearity		V <sub>S</sub> = 5.5V, G = 10 or 50		±0.005	±0.015		*	*	% of FSR
Over Temperature		_			±0.015			*	% of FSR
OUTPUT									
Voltage Output Swing from Rail		$R_L = 10k\Omega, G_{ERR} < 0.1\%$		5	10		*	*	mV
Over Temperature					10			*	mV
Short-Circuit Current		Short Circuit to Ground		±50			*		mA
Capacitance Load (stable operation)	)		Se	e Typical Cu	irve		*		
FREQUENCY RESPONSE									
Bandwidth, -3dB	BW	G = 10		550			*		kHz
		G = 50		110			*		kHz
Slew Rate	SR	$V_S = 5.5V, C_L = 100pF$		6.5			*		V/μs
Settling Time: 0.1%	t <sub>S</sub>	$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 10$		5			*		μs
		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 50$		11			*		μs
0.01%		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 10$		8			*		μs
		$V_S = 5.5V, V_O = 2V \text{ Step, } C_L = 100pF, G = 50$		15			*		μs
Overload Recovery		50% Input Overload		0.2			*		μs
Total Harmonic Distortion + Noise	THD+N		Se	e Typical Cu	ırve		*		
POWER SUPPLY									
Specified Voltage Range			+2.7		+5.5	*		*	V
Operating Voltage Range				+2.5 to +6			*		V
Quiescent Current		$V_{IN} = 0, I_{O} = 0$		1.7	2.1		*	*	mA
Over Temperature		$V_{IN} = 0$ , $I_O = 0$			2.8			*	mA
TEMPERATURE RANGE									1
Specified Range			-55		+125	*		*	°C
			-65		+150	*		*	°C
Operating Range					1 .450		1	1 .	
			-65		+150	*		*	°C
Operating Range Storage Range Thermal Resistance	$ heta_{\sf JA}$		<del>-</del> 65		+150	*		*	
Storage Range	$ heta_{\sf JA}$		<del>-</del> 65	150 150	+150	*	*	*	°C/W

<sup>\*</sup> Same as INA155E, U.

NOTES: (1) For further information, refer to typical performance curves on common-mode input range. (2) Operation above (V+) - 1.8V (max) results in reduced common-mode rejection. See discussion and Figure 6 in the text of this data sheet. (3) Does not include error and TCR of additional optional gain-setting resistor in series with  $R_G$ , if used.



#### **PIN CONFIGURATION**



#### ABSOLUTE MAXIMUM RATINGS(1)

Supply Voltage, V+ to V	7.5V
Signal Input Terminals, Voltage(2) (V-	-) $-$ 0.5V to (V+) + 0.5V
Current <sup>(2)</sup>	10mA
Output Short-Circuit(3)	Continuous
Operating Temperature	65°C to +150°C
Storage Temperature	65°C to +150°C
Junction Temperature	+150°C
Lead Temperature (soldering, 10s)	+300°C

NOTE: (1) Stresses above these ratings may cause permanent damage. Exposure to absolute maximum conditions for extended periods may degrade device reliability. These are stress ratings only, and functional operation of the device at these or any other conditions beyond those specified is not implied. (2) Input terminals are diode-clamped to the power supply rails. Input signals that can swing more that 0.5V beyond the supply rails should be current limited to 10mA or less. (3) Short circuit to ground.

# ELECTROSTATIC DISCHARGE SENSITIVITY

This integrated circuit can be damaged by ESD. Burr-Brown recommends that all integrated circuits be handled with appropriate precautions. Failure to observe proper handling and installation procedures can cause damage.

ESD damage can range from subtle performance degradation to complete device failure. Precision integrated circuits may be more susceptible to damage because very small parametric changes could cause the device not to meet its published specifications.

#### PACKAGE/ORDERING INFORMATION

PRODUCT	PACKAGE	PACKAGE DRAWING NUMBER	SPECIFIED TEMPERATURE RANGE	PACKAGE MARKING	ORDERING NUMBER <sup>(1)</sup>	TRANSPORT MEDIA
INA155U	SO-8	182	-55°C to +125°C	INA155U	INA155U	Rails
"	n n	"	"	"	INA155U/2K5	Tape and Reel
INA155UA	SO-8	182	-55°C to +125°C	INA155UA	INA155UA	Rails
"	n n	"	"	"	INA155UA/2K5	Tape and Reel
INA155E	MSOP-8	337	-55°C to +125°C	A55	INA155E/250	Tape and Reel
"	n n	"	"	"	INA155E/2K5	Tape and Reel
INA155EA	MSOP-8	337	-55°C to +125°C	A55	INA155EA/250	Tape and Reel
"	n n	"	"	"	INA155EA/2K5	Tape and Reel


NOTES: (1) Models with a slash (/) are available only in Tape and Reel in the quantities indicated (e.g., /2K5 indicates 2500 devices per reel). Ordering 2500 pieces of "INA155UA/2K5" will get a single 2500-piece Tape and Reel.


The information provided herein is believed to be reliable; however, BURR-BROWN assumes no responsibility for inaccuracies or omissions. BURR-BROWN assumes no responsibility for the use of this information, and all use of such information shall be entirely at the user's own risk. Prices and specifications are subject to change without notice. No patent rights or licenses to any of the circuits described herein are implied or granted to any third party. BURR-BROWN does not authorize or warrant any BURR-BROWN product for use in life support devices and/or systems.





# TYPICAL PERFORMANCE CURVES


At  $T_A = +25^{\circ}C$ ,  $V_S = 5.5V$ ,  $R_L = 10k\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.


















# TYPICAL PERFORMANCE CURVES (Cont.)


At  $T_A$  = +25°C,  $V_S$  = 5.5V,  $R_L$  = 10k $\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.




















# TYPICAL PERFORMANCE CURVES (Cont.)


At  $T_A = +25^{\circ}C$ ,  $V_S = 5.5V$ ,  $R_L = 10k\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.


















# TYPICAL PERFORMANCE CURVES (Cont.)


At  $T_A$  = +25°C,  $V_S$  = 5.5V,  $R_L$  = 10k $\Omega$  connected to  $V_S/2$ .  $R_G$  pins open (G = 10), and Ref =  $V_S/2$ , unless otherwise noted.













# APPLICATIONS INFORMATION

Figure 1 shows the basic connections required for operation of the INA155. Applications with noisy or high impedance power supplies may require decoupling capacitors close to the device pins as shown.

The output is referred to the output reference terminal, Ref, which is normally set to  $V_S/2$ . This must be a low-impedance connection to ensure good common-mode rejection. A resistance of  $200\Omega$  in series with the Ref pin will cause a typical device to degrade to approximately 80dB CMRR.

In addition, for the G=50 configuration, the connection between pins 1 and 8 must be low-impedance. A connection impedance of  $20\Omega$  can cause a 0.2% shift in gain error.

#### **OPERATING VOLTAGE**

The INA155 is fully specified and guaranteed over the supply range +2.7V to +5.5V, with key parameters guaranteed over the temperature range of -55°C to +125°C. Parameters that vary significantly with operating voltages, load conditions or temperature are shown in the Typical Performance Curves.

The INA155 can be operated from either single or dual power supplies. By adjusting the voltage applied to the reference terminal, the input common-mode voltage range and the output range can be adjusted within the bounds shown in the Typical Performance Curves. Figure 2 shows a bridge amplifier circuit operated from a single +5V power supply. The bridge provides a relatively small differential voltage on top of an input common-mode voltage near 2.5V.





FIGURE 1. Basic Connections.



9

FIGURE 2. Single-Supply Bridge Amplifier.

#### **SETTING THE GAIN**

Gain of 10 is achieved simply by leaving the two gain pins (1 and 8) open. Gain of 50 is achieved by connecting the gain pins together directly. In the G=10 configuration, the gain error is less than 0.1%. In the G=50 configuration, the gain error is less than 0.25%.

Gain can be set to any value between 10 and 50 by connecting a resistor  $R_G$  between the gain pins according to the following equation:

$$10 + 400k\Omega/(10k\Omega + R_G) \tag{1}$$

This is demonstrated in Figure 1 and is shown with the commonly used gains and resistor  $R_G$  values. However, because the absolute value of internal resistors is not guaranteed, using the INA155 in this configuration will increase the gain error and gain error drift with temperature, as shown in Figure 3.




FIGURE 3. Typical Gain Error and Gain Error Drift with External Resistor.

#### **OFFSET TRIMMING**

The INA155 is laser trimmed for low offset voltage. In most applications, no external offset adjustment is required. However, if necessary, the offset can be adjusted by applying a correction voltage to the reference terminal. Figure 4 shows




FIGURE 4. Optional Trimming of Output Offset Voltage.

INA155

an optional circuit for trimming the output offset voltage. The voltage applied to the Ref terminal is added to the output signal. An op amp buffer is used to provide low impedance at the Ref terminal to preserve good commonmode rejection.

#### INPUT BIAS CURRENT RETURN

The input impedance of the INA155 is extremely high—approximately  $10^{13}\Omega$ , making it ideal for use with high-impedance sources. However, a path must be provided for the input bias current of both inputs. This input bias current is less than 10pA and is virtually independent of the input voltage.

Input circuitry must provide a path for this input bias current for proper operation. Figure 5 shows various provisions for an input bias current path. Without a bias current path, the inputs will float to a potential that exceeds the commonmode range and the input amplifier will saturate.

If the differential source resistance is low, the bias current return path can be connected to one input (see the thermocouple in Figure 5). With higher source impedance, using two equal resistors provides a balanced input with advantages of lower input offset voltage due to bias current and better high-frequency common-mode rejection.




FIGURE 5. Providing an Input Common-Mode Current Path.

#### INPUT COMMON-MODE RANGE

The input common-mode range of the INA155 for various operating conditions is shown the in Typical Performance Curves. The common-mode input range is limited by the output voltage swing of A1, an internal circuit node. For the G = 10 configuration, output voltage of A1 can be expressed as:

$$V_{OUTA1} = -\frac{1}{9}V_{REF} + (1 + \frac{1}{9}) V_{IN}$$
 (2)

Using this equation given that the output of A1 can swing to within 10mV of either rail, the input common-mode voltage range can be calculated. When the input common-mode range is exceeded (A1's output is saturated), A2 can still be in linear operation and respond to changes in the non-inverting input voltage. However, the output voltage will be invalid.

The common-mode range for the G=50 configuration is included in the Typical Performance Curve, "Input Common-Mode Range vs Output Voltage."

#### INPUT RANGE FOR BEST ACCURACY

The internal amplifiers have rail-to-rail input stages, achieved by using complementary n- and p-channel input pairs. The common-mode input voltage determines whether the p-channel or the n-channel input stage is operating. The transition between the input stages is gradual and occurs between (V+) - 1.8V to (V+) - 0.8V. Due to these characteristics operating the INA155 with input voltages within the transition region of (V+) - 1.8V to (V+) - 0.8V results in a shift in input offset voltage and reduced common-mode and power supply rejection performance. Typical patterns of the offset voltage change throughout the input common-mode range are illustrated in Figure 6. The INA155 can be operated below or above the transition region with excellent results. Figure 7 demonstrates the use of the INA155 in a single-supply, high-side current monitor. In this application, the INA155 is operated above the transition region.

#### **RAIL-TO-RAIL OUTPUT**

A class AB output stage with common-source transistors is used to achieve rail-to-rail output. For resistive loads greater than  $10k\Omega$ , the output voltage can swing to within a few millivolts of the supply rail while maintaining low gain error. For heavier loads and over temperature, see the typical performance curve "Output Voltage Swing vs Output Current." The INA155's low output impedance at high frequencies makes it suitable for directly driving Capacitive Digital-to-Analog (CDAC) input A/D converters, as shown in Figure 9.

### INPUT PROTECTION

Device inputs are protected by ESD diodes that will conduct if the input voltages exceed the power supplies by more than 500mV. Momentary voltages greater than 500mV beyond the power supply can be tolerated if the current on the input pins is limited to 10mA. This is easily accomplished with input resistors  $R_{LIM}$  as shown in Figure 8. Many input signals are inherently current-limited to less than 10mA, therefore, a limiting resistor is not required.




FIGURE 6. Input Offset Voltage Changes with Common-Mode Voltage.




FIGURE 7. Single-Supply, High-Side Current Monitor.




FIGURE 8. Input Current Protection for Voltages Exceeding the Supply Voltage.




FIGURE 9. INA155 Directly Drives Capacitive-Input, High-Speed A/D Converter.







10-Jun-2014

## **PACKAGING INFORMATION**

Orderable Device	Status	Package Type	Package Drawing	Pins	Package Qty	Eco Plan	Lead/Ball Finish	MSL Peak Temp	Op Temp (°C)	Device Marking	Samples
INA155E/250	ACTIVE	VSSOP	DGK	8	250	Green (RoHS & no Sb/Br)	CU NIPDAUAG	Level-2-260C-1 YEAR	-40 to 85	A55	Samples
INA155E/250G4	ACTIVE	VSSOP	DGK	8	250	Green (RoHS & no Sb/Br)	CU NIPDAUAG	Level-2-260C-1 YEAR	-40 to 85	A55	Samples
INA155E/2K5	ACTIVE	VSSOP	DGK	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAUAG	Level-2-260C-1 YEAR		A55	Samples
INA155EA/250	ACTIVE	VSSOP	DGK	8	250	Green (RoHS & no Sb/Br)	CU NIPDAUAG	Level-2-260C-1 YEAR		A55	Samples
INA155EA/250G4	ACTIVE	VSSOP	DGK	8	250	Green (RoHS & no Sb/Br)	CU NIPDAUAG	Level-2-260C-1 YEAR		A55	Samples
INA155EA/2K5	ACTIVE	VSSOP	DGK	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAUAG	Level-2-260C-1 YEAR		A55	Samples
INA155EA/2K5G4	ACTIVE	VSSOP	DGK	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAUAG	Level-2-260C-1 YEAR		A55	Samples
INA155U	ACTIVE	SOIC	D	8	75	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-2-260C-1 YEAR		INA 155U	Samples
INA155U/2K5	ACTIVE	SOIC	D	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-2-260C-1 YEAR		INA 155U	Samples
INA155U/2K5G4	ACTIVE	SOIC	D	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-2-260C-1 YEAR		INA 155U	Samples
INA155UA	ACTIVE	SOIC	D	8	75	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-2-260C-1 YEAR		INA 155U A	Samples
INA155UA/2K5	ACTIVE	SOIC	D	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-2-260C-1 YEAR		INA 155U A	Samples
INA155UA/2K5G4	ACTIVE	SOIC	D	8	2500	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-2-260C-1 YEAR		INA 155U A	Samples
INA155UAG4	ACTIVE	SOIC	D	8	75	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-2-260C-1 YEAR		INA 155U A	Samples
INA155UG4	ACTIVE	SOIC	D	8	75	Green (RoHS & no Sb/Br)	CU NIPDAU	Level-2-260C-1 YEAR		INA 155U	Samples



## PACKAGE OPTION ADDENDUM

10-Jun-2014

(1) The marketing status values are defined as follows:

ACTIVE: Product device recommended for new designs.

LIFEBUY: TI has announced that the device will be discontinued, and a lifetime-buy period is in effect.

NRND: Not recommended for new designs. Device is in production to support existing customers, but TI does not recommend using this part in a new design.

PREVIEW: Device has been announced but is not in production. Samples may or may not be available.

**OBSOLETE:** TI has discontinued the production of the device.

(2) Eco Plan - The planned eco-friendly classification: Pb-Free (RoHS), Pb-Free (RoHS Exempt), or Green (RoHS & no Sb/Br) - please check http://www.ti.com/productcontent for the latest availability information and additional product content details.

**TBD:** The Pb-Free/Green conversion plan has not been defined.

**Pb-Free (RoHS):** TI's terms "Lead-Free" or "Pb-Free" mean semiconductor products that are compatible with the current RoHS requirements for all 6 substances, including the requirement that lead not exceed 0.1% by weight in homogeneous materials. Where designed to be soldered at high temperatures, TI Pb-Free products are suitable for use in specified lead-free processes.

**Pb-Free (RoHS Exempt):** This component has a RoHS exemption for either 1) lead-based flip-chip solder bumps used between the die and package, or 2) lead-based die adhesive used between the die and leadframe. The component is otherwise considered Pb-Free (RoHS compatible) as defined above.

Green (RoHS & no Sb/Br): TI defines "Green" to mean Pb-Free (RoHS compatible), and free of Bromine (Br) and Antimony (Sb) based flame retardants (Br or Sb do not exceed 0.1% by weight in homogeneous material)

- (3) MSL, Peak Temp. The Moisture Sensitivity Level rating according to the JEDEC industry standard classifications, and peak solder temperature.
- (4) There may be additional marking, which relates to the logo, the lot trace code information, or the environmental category on the device.
- (5) Multiple Device Markings will be inside parentheses. Only one Device Marking contained in parentheses and separated by a "~" will appear on a device. If a line is indented then it is a continuation of the previous line and the two combined represent the entire Device Marking for that device.
- (6) Lead/Ball Finish Orderable Devices may have multiple material finish options. Finish options are separated by a vertical ruled line. Lead/Ball Finish values may wrap to two lines if the finish value exceeds the maximum column width.


**Important Information and Disclaimer:** The information provided on this page represents TI's knowledge and belief as of the date that it is provided. TI bases its knowledge and belief on information provided by third parties, and makes no representation or warranty as to the accuracy of such information. Efforts are underway to better integrate information from third parties. TI has taken and continues to take reasonable steps to provide representative and accurate information but may not have conducted destructive testing or chemical analysis on incoming materials and chemicals. TI and TI suppliers consider certain information to be proprietary, and thus CAS numbers and other limited information may not be available for release.


In no event shall TI's liability arising out of such information exceed the total purchase price of the TI part(s) at issue in this document sold by TI to Customer on an annual basis.

PACKAGE MATERIALS INFORMATION

www.ti.com 14-Aug-2013

## TAPE AND REEL INFORMATION





Α0	Dimension designed to accommodate the component width
B0	Dimension designed to accommodate the component length
	Dimension designed to accommodate the component thickness
W	Overall width of the carrier tape
P1	Pitch between successive cavity centers


## QUADRANT ASSIGNMENTS FOR PIN 1 ORIENTATION IN TAPE



#### \*All dimensions are nominal

Device	Package Type	Package Drawing		SPQ	Reel Diameter (mm)	Reel Width W1 (mm)	A0 (mm)	B0 (mm)	K0 (mm)	P1 (mm)	W (mm)	Pin1 Quadrant
INA155E/250	VSSOP	DGK	8	250	180.0	12.4	5.3	3.4	1.4	8.0	12.0	Q1
INA155E/2K5	VSSOP	DGK	8	2500	330.0	12.4	5.3	3.4	1.4	8.0	12.0	Q1
INA155EA/250	VSSOP	DGK	8	250	180.0	12.4	5.3	3.4	1.4	8.0	12.0	Q1
INA155EA/2K5	VSSOP	DGK	8	2500	330.0	12.4	5.3	3.4	1.4	8.0	12.0	Q1
INA155U/2K5	SOIC	D	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1
INA155UA/2K5	SOIC	D	8	2500	330.0	12.4	6.4	5.2	2.1	8.0	12.0	Q1

www.ti.com 14-Aug-2013



\*All dimensions are nominal

Device	Package Type	Package Drawing	Pins	SPQ	Length (mm)	Width (mm)	Height (mm)
INA155E/250	VSSOP	DGK	8	250	210.0	185.0	35.0
INA155E/2K5	VSSOP	DGK	8	2500	367.0	367.0	35.0
INA155EA/250	VSSOP	DGK	8	250	210.0	185.0	35.0
INA155EA/2K5	VSSOP	DGK	8	2500	367.0	367.0	35.0
INA155U/2K5	SOIC	D	8	2500	367.0	367.0	35.0
INA155UA/2K5	SOIC	D	8	2500	367.0	367.0	35.0

#### IMPORTANT NOTICE

Texas Instruments Incorporated and its subsidiaries (TI) reserve the right to make corrections, enhancements, improvements and other changes to its semiconductor products and services per JESD46, latest issue, and to discontinue any product or service per JESD48, latest issue. Buyers should obtain the latest relevant information before placing orders and should verify that such information is current and complete. All semiconductor products (also referred to herein as "components") are sold subject to TI's terms and conditions of sale supplied at the time of order acknowledgment.

TI warrants performance of its components to the specifications applicable at the time of sale, in accordance with the warranty in TI's terms and conditions of sale of semiconductor products. Testing and other quality control techniques are used to the extent TI deems necessary to support this warranty. Except where mandated by applicable law, testing of all parameters of each component is not necessarily performed.

TI assumes no liability for applications assistance or the design of Buyers' products. Buyers are responsible for their products and applications using TI components. To minimize the risks associated with Buyers' products and applications, Buyers should provide adequate design and operating safeguards.

TI does not warrant or represent that any license, either express or implied, is granted under any patent right, copyright, mask work right, or other intellectual property right relating to any combination, machine, or process in which TI components or services are used. Information published by TI regarding third-party products or services does not constitute a license to use such products or services or a warranty or endorsement thereof. Use of such information may require a license from a third party under the patents or other intellectual property of the third party, or a license from TI under the patents or other intellectual property of TI.

Reproduction of significant portions of TI information in TI data books or data sheets is permissible only if reproduction is without alteration and is accompanied by all associated warranties, conditions, limitations, and notices. TI is not responsible or liable for such altered documentation. Information of third parties may be subject to additional restrictions.

Resale of TI components or services with statements different from or beyond the parameters stated by TI for that component or service voids all express and any implied warranties for the associated TI component or service and is an unfair and deceptive business practice. TI is not responsible or liable for any such statements.

Buyer acknowledges and agrees that it is solely responsible for compliance with all legal, regulatory and safety-related requirements concerning its products, and any use of TI components in its applications, notwithstanding any applications-related information or support that may be provided by TI. Buyer represents and agrees that it has all the necessary expertise to create and implement safeguards which anticipate dangerous consequences of failures, monitor failures and their consequences, lessen the likelihood of failures that might cause harm and take appropriate remedial actions. Buyer will fully indemnify TI and its representatives against any damages arising out of the use of any TI components in safety-critical applications.

In some cases, TI components may be promoted specifically to facilitate safety-related applications. With such components, TI's goal is to help enable customers to design and create their own end-product solutions that meet applicable functional safety standards and requirements. Nonetheless, such components are subject to these terms.

No TI components are authorized for use in FDA Class III (or similar life-critical medical equipment) unless authorized officers of the parties have executed a special agreement specifically governing such use.

Only those TI components which TI has specifically designated as military grade or "enhanced plastic" are designed and intended for use in military/aerospace applications or environments. Buyer acknowledges and agrees that any military or aerospace use of TI components which have *not* been so designated is solely at the Buyer's risk, and that Buyer is solely responsible for compliance with all legal and regulatory requirements in connection with such use.

TI has specifically designated certain components as meeting ISO/TS16949 requirements, mainly for automotive use. In any case of use of non-designated products, TI will not be responsible for any failure to meet ISO/TS16949.

Products Applications

Audio www.ti.com/audio Automotive and Transportation www.ti.com/automotive Communications and Telecom Amplifiers amplifier.ti.com www.ti.com/communications **Data Converters** dataconverter.ti.com Computers and Peripherals www.ti.com/computers **DLP® Products** www.dlp.com Consumer Electronics www.ti.com/consumer-apps

DSP **Energy and Lighting** dsp.ti.com www.ti.com/energy Clocks and Timers www.ti.com/clocks Industrial www.ti.com/industrial Interface interface.ti.com Medical www.ti.com/medical logic.ti.com Logic Security www.ti.com/security

Power Mgmt power.ti.com Space, Avionics and Defense www.ti.com/space-avionics-defense

Microcontrollers <u>microcontroller.ti.com</u> Video and Imaging <u>www.ti.com/video</u>

RFID <u>www.ti-rfid.com</u>

OMAP Applications Processors <a href="www.ti.com/omap">www.ti.com/omap</a> TI E2E Community <a href="e2e.ti.com">e2e.ti.com</a>

Wireless Connectivity <u>www.ti.com/wirelessconnectivity</u>