



# **MPY100**

# **MULTIPLIER-DIVIDER**

# **FEATURES**

- LOW COST
- DIFFERENTIAL INPUT
- ACCURACY 100% TESTED AND GUARANTEED
- NO EXTERNAL TRIMMING REQUIRED
- LOW NOISE: 90µVrms, 10Hz to 10kHz
- HIGHLY RELIABLE ONE-CHIP DESIGN
- DIP OR TO-100 TYPE PACKAGE
- WIDE TEMPERATURE OPERATION


### **APPLICATIONS**

- MULTIPLICATION
- DIVISION
- SQUARING
- SQUARE ROOT
- LINEARIZATION
- POWER COMPUTATION
- ANALOG SIGNAL PROCESSING
- ALGEBRAIC COMPUTATION
- TRUE RMS-TO-DC CONVERSION

### **DESCRIPTION**

The MPY100 multiplier-divider is a low cost precision device designed for general purpose application. In addition to four-quadrant multiplication, it also performs analog square root and division without the bother of external amplifiers or potentiometers. Laser-trimmed one-chip design offers the most in highly

reliable operation with guaranteed accuracies. Because of the internal reference and pretrimmed accuracies the MPY100 does not have the restrictions of other low cost multipliers. It is available in both TO-100 and DIP ceramic packages.



International Airport Industrial Park • Mailing Address: PO Box 11400 • Tucson, AZ 85734 • Street Address: 6730 S. Tucson Blvd. • Tucson, AZ 85706

Tel: (520) 746-1111 • Twx: 910-952-1111 • Cable: BBRCORP • Telex: 066-6491 • FAX: (520) 889-1510 • Immediate Product Info: (800) 548-6132

# **SPECIFICATIONS**

At T<sub>A</sub> = +25°C and  $\pm V_S$  = 15VDC, unless otherwise specified.

			MPY100/	Α		MPY100B/	С		MPY100S		1
PARAMETER	CONDITIONS	MIN	TYP	MAX	MIN	TYP	MAX	MIN	TYP	MAX	UNITS
MULTIPLIER PERFORM											
Transfer Function		(X,	$\frac{(Y_1 - X_2)(Y_1 - Y_2)}{10}$	. 7		*/*			*		
			10	— + Z <sub>2</sub>							
Total Error	-10V ≤ X, Y ≤ 10V										
Initial	$T_A = +25^{\circ}C$			±2.0			±1.0/0.5			±0.5	% FSR
vs Temperature	-25°C ≤ T <sub>A</sub> ≤ +85°C		±0.017	±0.05		±0.008/0.008					% FSR/°C
vs Temperature	-55°C ≤ T <sub>A</sub> ≤ +125°C								±0.025	±0.05	% FSR/°C
vs Supply <sup>(1)</sup>	^		±0.05			*/*			*		% FSR/%
Individual Errors											
Output Offset											
Initial	$T_A = +25^{\circ}C$		±50	±100		±10/7	±50/25		±7	±50	mV
vs Temperature	$-25^{\circ}\text{C} \le \text{T}_{\text{A}} \le +85^{\circ}\text{C}$		±0.7	±2.0		±0.7/0.3	±2.0/±0.7				mV/°C
vs Temperature	$-55^{\circ}\text{C} \le \text{T}_{\text{A}} \le +125^{\circ}\text{C}$								±0.3	±0.7	mV/°C
vs Supply <sup>(1)</sup>			±0.25			*/*			*		mV/%
Scale Factor Error	T 0500										0/ 505
Initial	$T_A = +25^{\circ}C$		±0.12			*/*			Î		% FSR
vs Temperature	$-25^{\circ}\text{C} \le \text{T}_{\text{A}} \le +85^{\circ}\text{C}$ $-55^{\circ}\text{C} \le \text{T}_{\text{A}} \le +125^{\circ}\text{C}$		±0.008			-7-			10.000		% FSR/°C
vs Temperature	-55°C \(\sigma\) A \(\sigma\) +125°C		+0.05			*/*			±0.008		% FSR/*C
vs Supply <sup>(1)</sup>			±0.05			-7					% FSR %
Nonlinearity X Input	X = 20Vp-p; Y = ±10VDC		±0.08			*/*			*		% FSR
•	$X = 20Vp-p, Y = \pm 10VDC$ $Y = 20Vp-p: X = \pm 10VDC$		±0.08			*/*			*		% FSR
Feedthrough	f = 50Hz		±0.06			'					% F3K
X Input	X = 20Vp-p; Y = 0		100			30/30			30		mVp-p
Y Input	X = 20Vp-p, T = 0 Y = 20Vp-p; X = 0		6			*/*			*		mVp-p
vs Temperature	$-25^{\circ}\text{C} \le \text{T}_{\text{A}} \le +85^{\circ}\text{C}$		0.1			*/*					mVp-p/°C
vs Temperature	$-55^{\circ}\text{C} \le \text{T}_{\text{A}} \le 125^{\circ}\text{C}$		0.1			'			0.1		mVp-p/°C
vs Supply <sup>(1)</sup>	00 0 = 1 <sub>A</sub> = 120 0		0.15			*/*			*		mVp-p/%
					1	<del>-</del>					
DIVIDER PERFORMANC Transfer Function			1 10/7 – 7 )	ļ		*/*			*		
Transfer Function	$X_1 > X_2$	-	$\frac{10(Z_2 - Z_1)}{(X_1 - X_2)} +$	Y,		/					
			$(X_1 - X_2)$	ı							
Total Error (with	X = 10V										
external adjustments)	-10V ≤ Z ≤ +10V		±1.5			±0.75/0.35			±0.35		% FSR
	X = 1V										
	$-1V \le Z \le +1V$		±4.0			±2.0/1.0			±1.0		% FSR
	+0.2V ≤ X ≤ +10V		15.0			105/10			14.0		% FSR
	-10V ≤ Z ≤ +10V		±5.0			±2.5/1.0			±1.0		% F5K
SQUARER PERFORMAN	ICE										
Transfer Function			$\frac{(X_1 - X_2)^2}{10}$ +	7		*/*			*		
			10	<b>_</b> 2							
Total Error	-10V ≤ X ≤ +10V		±1.2			±0.6/0.3			±0.3		% FSR
					1						,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,
SQUARE ROOTER PER Transfer Function			10/7 7).	<u> </u>		*/*			*		
Total Error	$Z_1 < Z_2$ $1V \le Z \le 10V$	+1	$10(Z_2 - Z_1) + \pm 2$	^ <sub>2</sub>		±1/0.5			±0.5		% FSR
	1 V S Z S 10 V				1	1/0.5			±0.5		/0 F3K
AC PERFORMANCE											
Small-Signal Bandwidth			550			*/*			*		kHz
% Amplitude Error	Small-Signal		70			*/*			*		kHz
% (0.57°) Vector Error	Small-Signal		5			*/*			*		kHz
Full Power Bandwidth	$ V_0  = 10V, R_L = 2k\Omega$		320			*/*			*		kHz
Slew Rate	$ V_0  = 10V, R_L = 2k\Omega$		20			*/*			·		V/μs
Settling Time	$\varepsilon = \pm 1\%$ , $\Delta V_0 = 20V$		2			*/* */*			*		μs
Overload Recovery	50% Output Overload		0.2			-7-			-		μs
INPUT CHARACTERIST	cs										
Input Voltage Range											
Rated Operation		±10			*/*			*			V
Absolute Maximum	V V = 400			±V <sub>cc</sub>	1	l	*/*			*	V
Input Resistance	X, Y, Z <sup>(2)</sup>		10			*/*			*		MΩ
Input Bias Current	X, Y, Z		1.4			*/*			*		μΑ
OUTPUT CHARACTERIS	STICS										
Rated Output						1		1			
Voltage	$I_O = \pm 5mA$	±10			*/*			*			V
Current Output Resistance	$V_O = \pm 10V$ f = DC	±5	1.5		*/*	*/*		*			mA Ω



# SPECIFICATIONS (CONT)


At  $T_A = +25^{\circ}C$  and  $\pm V_S = 15VDC$ , unless otherwise specified.

			MPY100	4		MPY100B/	С		MPY100S		
PARAMETER	CONDITIONS	MIN	TYP	MAX	MIN	TYP	MAX	MIN	TYP	MAX	UNITS
OUTPUT NOISE VOLTA	<b>AGE</b> X = Y = 0										
f <sub>O</sub> = 1Hz			6.2			*/*			*		μV/√ <del>Hz</del>
$f_0 = 1kHz$			0.6			*/*			*		μV/√ <del>Hz</del>
I/f Corner Frequency			110			*/*			*		Hz
$f_B = 5Hz$ to $10kHz$			60			*/*			*		μVrms
$f_B = 5Hz$ to $5MHz$			1.3			*/*			*		mVrms
POWER SUPPLY REQU	POWER SUPPLY REQUIREMENTS										
Rated Voltage			±15			*/*			*		VDC
Operating Range	Derated Performance	±8.5		±20	*/*		*/*	*		*	VDC
Quiescent Current			±5.5			*/*			*		mA
TEMPERATURE RANGI	E (Ambient)										
Specification	, , ,	-25		+85	*/*		*/*	-55		+125	°C
Operating Range	Derated Performance	-55		+125	*/*		*/*	*		*	°C
Storage		-65		+150	*/*		*/*	*		*	°C

<sup>\*</sup> Same as MPY100A specification.

NOTES: (1) Includes effects of recommended null pots. (2)  $Z_2$  input resistance is 10M $\Omega$ , typical, with  $V_{OS}$  pin open. If  $V_{OS}$  pin is grounded or used for optional offset adjustment, the  $Z_2$  input resistance may be as low as 25k $\Omega$ 

#### **PIN CONFIGURATIONS**




NOTES: (1)  $V_{\rm OS}$  adjustment optional not normally recommended.  $V_{\rm OS}$  pin may be left open or grounded. (2) All unused input pins should be grounded.

#### **ABSOLUTE MAXIMUM RATINGS**

Supply	±20VDC
Internal Power Dissipation(1)	500mW
Differential Input Voltage(2)	±40VDC
Input Voltage Range <sup>(2)</sup>	±20VDC
Storage Temperature Range	65°C to +150°C
Operating Temperature Range	55°C to +125°C
Lead Temperature (soldering, 10s)	+300°C
Output Short-circuit Duration(3)	Continuous
Junction Temperature	

NOTES: (1) Package must be derated on  $\theta_{JC}=15^{\circ}\text{C/W}$  and  $\theta_{JA}=165^{\circ}\text{C/W}$  for the metal package and  $\theta_{JC}=35^{\circ}\text{C/W}$  and  $\theta_{JA}=220^{\circ}\text{C/W}$  for the ceramic package. (2) For supply voltages less than  $\pm 20\text{VDC}$ , the absolute maximum input voltage is equal to the supply voltage. (3) Short-circuit may be to ground only. Rating applies to +85°C ambient for the metal package and +65°C for the ceramic package.



NOTES: (1)  $V_{\rm OS}$  adjustment optional not normally recommended.  $V_{\rm OS}$  pin may be left open or grounded. (2) All unused input pins should be grounded.

#### **ORDERING INFORMATION**

MODEL	PACKAGE	TEMPERATURE RANGE
MPY100AG	14-Pin Ceramic DIP	-25°C to +85°C
MPY100AM	Metal TO-100	-25°C to +85°C
MPY100BG	14-Pin Ceramic DIP	-25°C to +85°C
MPY100BM	Metal TO-100	-25°C to +85°C
MPY100CG	14-Pin Ceramic DIP	-25°C to +85°C
MPY100CM	Metal TO-100	-25°C to +85°C
MPY100SG	14-Pin Ceramic DIP	-55°C to +125°C
MPY100SM	Metal TO-100	-55°C to +125°C


#### **PACKAGE INFORMATION**

MODEL	PACKAGE	PACKAGE DRAWING NUMBER <sup>(1)</sup>
MPY100AG	14-Pin Ceramic DIP	169
MPY100AM	Metal TO-100	007
MPY100BG	14-Pin Ceramic DIP	169
MPY100BM	Metal TO-100	007
MPY100CG	14-Pin Ceramic DIP	169
MPY100CM	Metal TO-100	007
MPY100SG	14-Pin Ceramic DIP	169
MPY100SM	Metal TO-100	007


NOTE: (1) For detailed drawing and dimension table, please see end of data sheet, or Appendix D of Burr-Brown IC Data Book.

<sup>\*/\*</sup> B/C grades same as MPY100A specification.


### SIMPLIFIED SCHEMATIC



### **CONNECTION DIAGRAM**



### **DICE INFORMATION**



PAD	FUNCTION
1	Y <sub>2</sub>
2	Y <sub>2</sub> V <sub>OS</sub> Z <sub>2</sub> X <sub>2</sub> X <sub>1</sub>
3	$Z_2$
4	X <sub>2</sub>
5	X <sub>1</sub>
6	V <sub>O</sub> Z <sub>1</sub> +V
7	Z <sub>1</sub>
8	
9	_V
10	Y <sub>1</sub>


Substrate Bias: -V<sub>CC</sub>


### **MECHANICAL INFORMATION**


	MILS (0.001")	MILLIMETERS
Die Size	107 x 93 ±5	2.72 x 2.36 ±0.13
Die Thickness	20 ±3	0.51 ±0.08
Min. Pad Size	4 x 4	0.10 x 0.10
Backing		Gold


# **TYPICAL PERFORMANCE CURVES**


At  $T_A$  = +25°C and  $\pm V_S$  = 15VDC, unless otherwise specified.

















# **TYPICAL PERFORMANCE CURVES (CONT)**

At  $T_A$  = +25°C and  $\pm V_S$  = 15VDC, unless otherwise specified.







# THEORY OF OPERATION

The MPY100 is a variable transconductance multiplier consisting of three differential voltage-to-current converters, a multiplier core and an output differential amplifier as illustrated in Figure 1.

The basic principle of the transconductance multiplier can be demonstrated by the differential stage in Figure 2.

For small values of the input voltage,  $V_1$ , that are much smaller than  $V_T$ , the transistor's thermal voltage, the differential output voltage,  $V_0$ , is:

$$V_O = g_m R_L V_1$$

The transconductance  $g_m$  of the stage is given by:

$$g_m = I_E/V_T$$




FIGURE 1. MPY100 Functional Block Diagram.




FIGURE 2. Basic Differential Stage as a Transconductance Multiplier.

and is modulated by the voltage, V2, to give

$$g_m \approx V_2/V_T R_E$$

Substituting this into the original equation yields the overall transfer function

$$V_{O} = g_{m}R_{L}V_{1} = V_{1}V_{2} (R_{L}/V_{T}R_{E})$$

which shows the output voltage to be the product of the two input voltages,  $V_1$  and  $V_2$ .

Variations in  $I_E$  due to  $V_2$  cause a large common-mode voltage swing in the circuit. The errors associated with this common-mode voltage can be eliminated by using two differential stages in parallel and cross-coupling their outputs as shown in Figure 3.




FIGURE 3. Cross-Coupled Differential Stages as a Variable-Transconductance Multiplier.

An analysis of the circuit in Figure 3 shows it to have the same overall transfer function as before:

$$V_{O} = V_{1}V_{2} (R_{L}/V_{T}R_{E}).$$

For input voltages larger than  $V_T$ , the voltage-to-current transfer characteristics of the differential pair  $Q_1$ ,  $Q_2$  or  $Q_3$  and  $Q_4$  are no longer linear. Instead, their collector currents are related to the applied voltage  $V_1$ 

$$\frac{I_1}{I_2} = \frac{I_3}{I_4} = e^{\frac{V_1}{V_T}}$$

The resultant nonlinearity can be overcome by developing  $V_1$  logarithmically to exactly cancel the exponential relationship just derived. This is done by diodes  $D_1$  and  $D_2$  in Figure 4.

The emitter degeneration resistors,  $R_X$  and  $R_Y$ , in Figure 4, provide a linear conversion of the input voltages to differential current,  $I_X$  and  $I_Y$ , where:



7

$$I_X = V_X/R_X$$
 and  $I_Y = V_Y/R_Y$ 

Analysis of Figure 4 shows the voltage V<sub>A</sub> to be:

$$V_A = (2R_L/I_1)(I_XI_Y)$$

Since  $I_X$  and  $I_Y$  are linearly related to the input voltages  $V_X$  and  $V_Y$ ,  $V_A$  may also be written:

$$V_A = KV_XV_Y$$

where K is a scale factor. In the MPY100, K is chosen to be 0.1.

The addition of the Z input alters the voltage V<sub>A</sub> to:

$$V_A = KV_XV_Y - V_Z$$

Therefore, the output of the MPY100 is:

$$V_O = A[KV_XV_Y - V_Z]$$

where A is the open-loop gain of the output amplifier. Writing this last equation in terms of the separate inputs to the MPY100 gives

$$V_{O} = A \left[ \frac{(X_{1} - X_{2})(Y_{1} - Y_{2})}{10} - (Z_{1} - Z_{2}) \right]$$

the transfer function of the MPY100.

#### WIRING PRECAUTIONS

In order to prevent frequency instability due to lead inductance of the power supply lines, each power supply should be bypassed. This should be done by connecting a  $10\mu F$  tantalum capacitor in parallel with a 1000pF ceramic capacitor from the  $+V_{CC}$  and  $-V_{CC}$  pins of the MPY100 to the power supply common. The connection of these capacitors should be as close to the MPY100 as practical.

#### **CAPACITIVE LOADS**

Stable operation is maintained with capacitive loads to 1000pF in all modes, except the square root mode for which 50pF is a safe upper limit. Higher capacitive loads can be driven if a  $100\Omega$  resistor is connected in series with the MPY100's output.

# **DEFINITIONS**

#### **TOTAL ERROR (Accuracy)**

Total error is the actual departure of the multiplier output voltage form the ideal product of its input voltages. It includes the sum of the effects of input and output DC offsets, gain error and nonlinearity.

#### **OUTPUT OFFSET**

Output offset is the output voltage when both inputs  $V_{\rm X}$  and  $V_{\rm Y}$  are 0V.

#### **SCALE FACTOR ERROR**

Scale factor error is the difference between the actual scale factor and the ideal scale factor.

#### **NONLINEARITY**

Nonlinearity is the maximum deviation from a best straightline (curve fitting on input-output graph) expressed as a percent of peak-to-peak full scale output.

#### **FEEDTHROUGH**

Feedthrough is the signal at the output for any value of  $V_{\rm X}$  or  $V_{\rm Y}$  within the rated range, when the other input is zero.




FIGURE 4. MPY100 Simplified Circuit Diagram.

#### SMALL SIGNAL BANDWIDTH

Small signal bandwidth is the frequency at which the output is down 3dB from its low-frequency value for nominal output amplitude of 10% of full scale.

#### 1% AMPLITUDE ERROR

The 1% amplitude error is the frequency the output amplitude is in error by 1%, measured with an output amplitude of 10% of full scale.

#### 1% VECTOR ERROR

The 1% vector error is the frequency at which a phase error of 0.01 radians (0.57°) occurs. This is the most sensitive measure of dynamic error of a multiplier.

# TYPICAL APPLICATIONS

#### MULTIPLICATION

Figure 5 shows the basic connection for four-quadrant multiplication.

The MPY100 meets all of its specifications without trimming. Accuracy can, however be improved over a limited range by nulling the output offset voltage using the  $100\Omega$  optional balance potentiometer shown in Figure 5.

AC feedthrough may be reduced to a minimum by applying an external voltage to the X or Y input as shown in Figure 6

Z<sub>2</sub>, the optional summing input, may be used to sum a voltage into the output of the MPY100. If not used, this terminal, as well as the X and Y input terminals, should be grounded. All inputs should be referenced to power supply common.

Figure 7 shows how to achieve a scale factor larger than the nominal 1/10. In this case, the scale factor is unity which makes the transfer function

$$V_{O} = KV_{X}V_{Y} = K(X_{1} - X_{2})(Y_{1} - Y_{2})K = \begin{bmatrix} \frac{1 + (R_{1}/R_{2})}{10} \end{bmatrix}$$

This circuit has the disadvantage of increasing the output offset voltage by a factor of 10, which may require the use of the optional balance control as in Figure 1 for some applications. In addition, this connection reduces the small signal bandwidth to about 50kHz.

#### **DIVISION**

Figure 8 shows the basic connection for two-quadrant division. This configuration is a multiplier-inverted analog divider, i.e., a multiplier connected in the feedback loop of an operational amplifier. In the case of the MPY100, this operational amplifier is the output amplifier shown in Figure 1.

The divider error with a multiplier-inverted analog divider is approximately:

$$\epsilon_{DIVIDER} = 10 \ \epsilon_{MULTIPLIER}/(X_1 - X_2)$$

It is obvious from this error equation that divider error becomes excessively large for small values of  $X_1 - X_2$ . A 10-to-1 denominator range is usually the practical limit. If more accurate division is required over a wide range of denominator voltages, an externally generated voltage may be




FIGURE 5. Multiplier Connection.




FIGURE 6. Optional Trimming Configuration.




FIGURE 7. Connection for Unity Scale Factor.




FIGURE 8. Divider Connection.



applied to the unused X-input (see Optional Trim Configuration). To trim, apply a ramp of +100 mV to +1 V at 100 Hz to both  $X_1$  and  $Z_1$  if  $X_2$  is used for offset adjustment, otherwise reverse the signal polarity and adjust the trim voltage to minimize the variation in the output. An alternative to this procedure would be to use the Burr-Brown DIV100, a precision log-antilog divider.

#### **SQUARING**




FIGURE 9. Squarer Connection.

#### **SQUARE ROOT**

Figure 10 shows the connection for taking the square root of the voltage  $V_Z$ . The diode prevents a latching condition which could occur if the input momentarily changed polarity. This latching condition is not a design flaw in the MPY100, but occurs when a multiplier is connected in the feedback loop of an operational amplifier to perform square root functions.

The load resistance,  $R_{L,}$  must be in the range of  $10k\Omega \le R_L \le 1M\Omega$ . This resistance must be in the circuit as it provides the current necessary to operate the diode.

#### PERCENTAGE COMPUTATION

The circuit of Figure 11 has a sensitivity of 1V/% and is capable of measuring 10% deviations. Wider deviation can be measured by decreasing the ratio of  $R_2/R_1$ .

#### **BRIDGE LINEARIZATION**

The use of the MPY100 to linearize the output from a bridge circuit makes the output  $V_{\rm O}$  independent of the bridge supply voltage. See Figure 12.

#### TRUE RMS-TO-DC CONVERSION

The rms-to-DC conversion circuit of Figure 13 gives greater accuracy and bandwidth but with less dynamic range than most rms-to-DC converters.

### SINE FUNCTION GENERATOR

The circuit in Figure 14 uses implicit feedback to implement the following sine function approximation:

$$V_O = (1.5715V_1 - 0.004317V_1^3)/(1 + 0.001398V_1^2)$$
  
= 10 sin (9V<sub>1</sub>)

# BURR-BROWN® MPY100

#### MORE CIRCUITS

The theory and procedures for developing virtually any function generator or linearization circuit can be found in the Burr-Brown/McGraw Hill book "FUNCTION CIRCUITS - Design and Applications."




FIGURE 10. Square Root Connection.




FIGURE 11. Percentage Computation.




FIGURE 12. Bridge Linearization.




FIGURE 13. True RMS-to-DC Conversion.




FIGURE 14. Sine Function Generator




FIGURE 15. Single-Phase Instantaneous and Real Power Measurement.

The information provided herein is believed to be reliable; however, BURR-BROWN assumes no responsibility for inaccuracies or omissions. BURR-BROWN assumes no responsibility for the use of this information, and all use of such information shall be entirely at the user's own risk. Prices and specifications are subject to change without notice. No patent rights or licenses to any of the circuits described herein are implied or granted to any third party. BURR-BROWN does not authorize or warrant any BURR-BROWN product for use in life support devices and/or systems.



#### **IMPORTANT NOTICE**

Texas Instruments and its subsidiaries (TI) reserve the right to make changes to their products or to discontinue any product or service without notice, and advise customers to obtain the latest version of relevant information to verify, before placing orders, that information being relied on is current and complete. All products are sold subject to the terms and conditions of sale supplied at the time of order acknowledgment, including those pertaining to warranty, patent infringement, and limitation of liability.

TI warrants performance of its semiconductor products to the specifications applicable at the time of sale in accordance with TI's standard warranty. Testing and other quality control techniques are utilized to the extent TI deems necessary to support this warranty. Specific testing of all parameters of each device is not necessarily performed, except those mandated by government requirements.

Customers are responsible for their applications using TI components.

In order to minimize risks associated with the customer's applications, adequate design and operating safeguards must be provided by the customer to minimize inherent or procedural hazards.

TI assumes no liability for applications assistance or customer product design. TI does not warrant or represent that any license, either express or implied, is granted under any patent right, copyright, mask work right, or other intellectual property right of TI covering or relating to any combination, machine, or process in which such semiconductor products or services might be or are used. TI's publication of information regarding any third party's products or services does not constitute TI's approval, warranty or endorsement thereof.

Copyright © 2000, Texas Instruments Incorporated